

Application Assessment Panel Minutes

Tuesday 27 February 2007

TABLE OF CONTENTS

D1	Confirmation of Minutes of meeting held on 20 February 2007	3
D2	DA716/2006 – 24 Glenmore Road, Paddington – Alterations & additions to gallery – 17/10/2006	3
D3	DA715/2006 – 26 Glenmore Road, Paddington – Alterations & additions to existing building & new one bedroom dwelling over gallery – 17/10/2006	3
D4	DA646/2006 – 21 Spencer Street, Rose Bay – Alterations & additions – 27/9/2006	3
D5	DA601/2006 – 335 & 337 Edgecliff Road, Woollahra – New double garage with timber deck over – 15/9/2006	3
D6	DA702/2006 – 8 Wyuna Road, Point Piper – New swimming pool & landscaping to front of property – 6/10/2006.....	3

Application Assessment Panel Minutes

**Minutes of the Meeting held on
Tuesday 27 February 2007 at 3.05pm**

Present: Application Assessment Panel:

T Tuxford (Manager – Compliance) (Chair)
C Bluett (Manager – Strategic Planning)
W Hatton (Director – Technical Services)

Staff: M Kelly (Secretary – Administration)
J La Posta (Senior Assessment Officer)
M McCubbery (Assessment Officer)
L Northridge (Senior Assessment Officer)

Apologies: Apologies were received and accepted from
Nil

Late Correspondence

Late correspondence was submitted to the Panel in relation to Items: D4, D5

Declarations of Interest

Nil

Items Decided by the Panel using its delegated authority (Items D1 to D6)

Item No: D1 Delegated to the Panel
Subject: **Confirmation of Minutes of meeting held on 20 February 2007**
Author: Marie Kelly, Secretary – Administration
File No: See Application Assessment Panel Minutes
Reason for Report: The Minutes of the Meeting of Tuesday 20 February 2007 were previously circulated. In accordance with the guidelines for Committees' operations it is now necessary that those Minutes be formally taken as read and confirmed.

(Bluett/Tuxford)

Resolved:

That the Minutes of the Application Assessment Panel Meeting of 20 February 2007 be taken as read and confirmed.

D2 DA716/2006 – 24 Glenmore Road, Paddington – Alterations & additions to gallery – 17/10/2006

Note: Mr B King Builder for the Applicant, addressed the Panel.

(Bluett/Hatton)

Resolved: Pursuant to Section 80(1) of the Environmental Planning and Assessment Act, 1979

THAT the Council, as the consent authority, grant development consent to Development Application No. 716/2006 for alterations and additions to gallery on land at 24 Glenmore Road Paddington, subject to the following conditions:

1. Approved Plans

This consent relates to the work, shown on plans numbered DA01 Rev B dated 28/09/2006, drawn by Indigo Design Group all of which carry a Council stamp "**Approved DA Plans**" and the signature of a Council officer, except where amended by the following conditions.

2. Materials

Details of the colour, texture and substance of all external materials must be submitted to Council or the accredited certifier prior to the issue of a Construction Certificate and are to be to the satisfaction of an authorised Council assessment officer or the accredited certifier. For properties that are located in a Conservation Area or that are Heritage Items, the proposed materials must be to the satisfaction of Council's Heritage Officer.

3. Requirement for a Construction Certificate

In accordance with the provisions of Section 81A of *the Environmental Planning and Assessment Act 1979*, the erection of the building must not be commenced until:

- (a) detailed plans and specifications of the building have been endorsed with a Construction Certificate by:
 - (i) Council; or
 - (ii) an accredited certifier; and
- (b) a principal certifying authority (PCA) has been appointed and the Council has been notified in writing of the appointment, and
- (c) at least two days notice, in writing, has been given to Council of the intention to commence work.

4. Hours of operation

The hours of operation are limited to the following:

Monday to Sunday 10am to 6pm.

5. Structural adequacy

A statement from a qualified practising Structural Engineer, certifying to the adequacy of the existing structural members, walls and footings to support the additional loads imposed by the proposed development, must be submitted with the Construction Certificate application.

This condition is imposed to ensure the structural integrity of the proposed building work.

6. Structural details

Structural engineering details and design calculations, prepared and certified by a qualified practising Structural Engineer, must be submitted with Construction Certificate application, for all reinforced concrete work, structural steel work, retaining walls, brick fences, shoring and underpinning, isolated piers, chimneys, parapets and other structural members.

This condition is imposed to ensure the structural integrity of the proposed building work.

7. Layout of buildings

The layout of all external walls, including retaining walls and contiguous piling must be checked and verified by survey prior to the commencement of construction to ensure that building construction complies with the development consent and does not encroach beyond the boundaries of the site.

8. Building Inspections

The Applicant, Owner and Builder, jointly and severally, must ensure that they call their Principal Certifying Authority ("the PCA") to carry out such critical phase building inspections required by the PCA, the PCA Service Agreement and that the PCA is satisfied with the level of compliance achieved before the Builder proceeds to the next phase of construction. Ample notice of required inspections must be given to the PCA in accordance with the PCA Service Agreement. The Applicant, Owner and Builder must comply with the PCA Service Agreement (Service Contract) and any lawful direction given by the Principal Certifying Authority.

Note: It is the responsibility of the PCA to ensure that critical phase building inspections are undertaken in accordance with a PCA Service Agreement and issue to the Applicant, Owner and Builder appropriate Notice under Section 109L of the Environmental Planning & Assessment Act 1979 ("the Act") where any breach of this consent occurs. Failure of the PCA to issue such notice may result in Council taking action under Section 109V of the Act.

Failure of the Applicant, Owner and Builder to comply with a PCA Service Agreement and comply with lawful directions of the PCA under this condition may result in Council issuing fines, notices, orders and commencing legal proceedings. Council will only enter into PCA Agreements with the Owner of the land being developed. Council, if appointed as the PCA, will report to the owner of the land being developed.

9. Erosion and sediment control

An erosion and sediment control plan, designed in accordance with the SSROC Soil and Water Management Brochures titled "Do it Right on Site" and the current version of the NSW Landcom publication "Managing Urban Stormwater: Soils and Construction" (*The Blue Book*), must be prepared to show erosion and sediment control measures which are to be installed. The Plan must be submitted to Council or the accredited certifier for approval before commencement of excavation or construction work.

10. Display of Council's warning sign for soil and water management

Throughout the demolition and construction, Council's warning sign for soil and water management must be displayed on the most prominent point of the building site, visible both from the street and site.

A copy of the sign is available from Council.

11. Demolition, excavation and construction hours

Demolition, excavation and construction work must not take place outside the hours of 7.00am to 5.30pm Monday to Friday and 7.00am to 1.00pm Saturday. No work and no deliveries are to take place on Sundays and public holidays. Noise from construction activities associated with the development must comply with the guidelines contained in the NSW EPA *Environmental Noise Control Manual* Chapter 171.

12. Standard for demolition

All demolition work must be undertaken in accordance with the provisions of *Australian Standard AS2601-2001: The Demolition of Structures*.

13. Demolition and disposal of hazardous materials

Removal, cleaning and disposal of lead-based paint must conform to the current EPA guidelines. Demolition of materials incorporating lead is to be conducted in strict accordance with sections 1.5, 1.6, 1.7, 3.1 and 3.9 of the *Australian Standard AS2601-1991, Demolition of Structures*.

Hazardous dust must not be allowed to escape from the site. The use of fine mesh dust proof screens or other measures is recommended. Any existing accumulations of dust (eg. ceiling voids and wall cavities) must be removed by the use of an industrial vacuum cleaner fitted with a high efficiency particulate air (HEPA) filter. All dusty surfaces and dust created from work must be suppressed by a fine water spray. Water must not be allowed to enter the street or stormwater systems. Demolition must not be performed during high winds, which may cause dust to spread beyond the site boundaries.

All contractors and employees directly involved in the removal of hazardous dusts and substances must wear protective equipment conforming to Australian Standard AS1716 Respiratory Protective Devices and must adopt work practices in accordance with the requirements of WorkSafe's *Control of Inorganic Lead At Work* (NOHSC:102(1994) and NOHSC:2015(1994)). All lead-contaminated materials must be disposed of in accordance with the EPA's requirements.

14. Stockpiles

Stockpiles of topsoil, sand, aggregate, soil or other material must not be located on any drainage line or easement, natural watercourse, footpath or roadway, or within the dripline of any Street Tree. Stockpiles within the construction site must be protected with adequate sediment controls, in accordance with Council's Code for Sediment Control.

15. Storage of materials and plant on Council's footpath

Building, excavation or demolition materials and plant must not be stored on Council's footpath and/or roadway unless prior written approval has been obtained from Council's Development Engineer.

16. Location of building operations

Building operations such as brick cutting, washing tools or brushes and mixing mortar must not take place on public roadways or footways or in any other location which could lead to the discharge of materials into the stormwater drainage system.

Footpaths, gutters and roadways must be swept regularly to keep them free from sediment.

17. Temporary disposal of roof water

Stormwater from any roof areas must be linked, via a temporary downpipe, to a Council approved stormwater disposal system immediately upon completion of the roof installation.

18. Site fencing

The site must be appropriately secured and fenced to the satisfaction of Council during demolition, excavation and construction work to ensure there are no unacceptable impacts on the amenity of adjoining properties. Permits for hoardings and or scaffolding on Council land must be obtained and clearly displayed on site.

19. Connection to existing drainage system

Stormwater run-off from the proposed addition must drain to the existing stormwater drainage system.

The existing stormwater drainage pipes on the property affected by the development must be checked and certified by a practising hydraulic engineer to ensure that existing stormwater pipes are in good condition and are operating satisfactorily. Certification and a plan showing pipe locations and diameters must be submitted to the Accredited Certifier prior to the issue of the final Occupation Certificate.

If the existing stormwater pipes are not in good condition and/or not operating satisfactorily, the existing drainage system must be upgraded. Certification and a plan showing pipe locations and diameters of the upgraded system must be submitted to the Accredited Certifier prior to the issue of the final Occupation Certificate.

Stormwater disposal is to comply with the requirements and conditions as set out in Council's Draft Stormwater Drainage Management DCP (Draft Version 1, Public Exhibition Copy dated 23/08/2004). This is available from Council's website <http://www.woollahra.nsw.gov.au>.

Note: connection of stormwater run-off to the Sydney Water sewer system is not permitted.

20. Toilet facilities

- (a) Toilet facilities must be provided, at or in the vicinity of the work site on which work involved in the erection or demolition of a building is being carried out, at the rate of one toilet for every 20 persons or part of 20 persons employed at the site.
- (b) Each toilet provided:
 - (a) must be a standard flushing toilet; and
 - (b) must be connected:
 - (i) to a public sewer; or
 - (ii) if connection to a public sewer is not practicable, to an accredited sewage management facility approved by the Council; or
 - (iii) if connection to a public sewer or an accredited sewage management facility is not practicable, to some other sewage management facility approved by the Council.
- (c) The provision of toilet facilities in accordance with this clause must be completed before any other work is commenced.

(d) In this condition:

accredited sewage management facility means a sewage management facility to which Division 4A of Part 3 of the Local Government (Approvals) Regulation 1993 applies, being a sewage management facility that is installed or constructed to a design or plan the subject of a certificate of accreditation referred to in Clause 95B of the Regulation.

approved by the Council means the subject of an approval in force under Division 1 of Part 3 of the *Local Government (Approvals) Regulation 1993*.

public sewer has the same meaning as it has in the *Local Government (Approvals) Regulation 1993*.

sewage management facility has the same meaning as it has in the Local Government (Approvals) Regulation 1993.

21. Compliance with Building Code of Australia

- (a) All building work must be carried out in accordance with the provisions of the *Building Code of Australia*.
- (b) This condition does not apply to the extent to which an exemption is in force under Clause 187 or 188, of the *Environmental Planning and Assessment Regulation 2000*, subject to the terms of any condition or requirement referred to in Clause 187 (6) or 188 (4) of the Regulation.

22. Signs to be erected on building and demolition sites

- (a) A sign must be erected in a prominent position on any work site on which work involved in the erection or demolition of a building is being carried out:
 - (i) stating that unauthorised entry to the work site is prohibited; and
 - (ii) showing the name of the person in charge of the work site and a telephone number at which that person may be contacted outside working hours.
- (b) Any such sign must be removed when the work has been completed.
- (c) This clause does not apply to:
 - (i) building work carried out inside an existing building; or
 - (ii) building work carried out on premises that must be occupied continuously (both during and outside working hours) while the work is being carried out.

23. Support for neighbouring buildings

- (a) If an excavation associated with the erection or demolition of a building extends below the level of the base of the footings of a building on an adjoining allotment of land, the person causing the excavation to be made:
 - (i) must preserve and protect the building from damage; and
 - (ii) if necessary, must underpin and support the building in an approved manner; and

- (iii) must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.
- (b) The owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this condition, whether carried out on the allotment of land being excavated or on the adjoining allotment of land.

In this condition, allotment of land includes a public road and any other public place.

24. Payment of Long Service Levy, Security, Development Levy and Fees (G.1)

The person(s) with the benefit of this consent must pay the following long service levy, security, development levy, and fees prior to the issue of any *construction certificate*, *subdivision certificate* or *occupation certificate*, as will apply.

The *certifying authority* must not issue any *Part 4A Certificate* until provided with the original receipt(s) for the payment of all of the following levy, security, contributions, and fees. Specifically:

- a) prior to the issue of a *construction certificate*, where a construction certificate is required; or
- b) prior to the issue of a *subdivision certificate*, where only a subdivision certificate is required; or
- c) prior to the issue of an *occupation certificate* in any other instance.

Description	Amount	Indexed	Council Fee Code
LONG SERVICE LEVY under Building and Construction Industry Long Service Payments Act 1986			
Long Service Levy (Currently 0.35% of contract value – subject to change. Contact LSL Corporation to confirm current rate)	Contact LSL Corporation	No	
SECURITY under section 80A(6) of the Environmental Planning and Assessment Act 1979			
Property Damage Security Deposit - Making good any damage caused to any property of the Council as a consequence of the doing of anything to which the consent relates.	\$4 000	Yes, yearly	T600
INSPECTION FEES under section 608 of the Local Government Act 1993			
Security Administration Fee	\$163	No	T16
TOTAL SECURITY, CONTRIBUTIONS, LEVIES AND FEES	\$4 163 Plus any relevant indexed amounts and long service levy		

How must the payments be made?

Payments must be made by:

1. Cash deposit with Council,
2. Credit card payment with Council, or
3. Bank cheque made payable to Woollahra Municipal Council.

The payment of a security may be made by a bank guarantee where:

- a) the guarantee is by an Australian bank for the amount of the total outstanding contribution;
- b) the bank unconditionally agrees to pay the guaranteed sum to the Council on written request by Council on completion of the development or no earlier than 12 months from the provision of the guarantee whichever occurs first;
- c) the bank agrees to pay the guaranteed sum without reference to the applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent; and
- d) the bank's obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required.

25. Occupation of premises

A person must not commence occupation or use of the whole or any part of a *new building* (within the meaning of section 109H (4) of the *Act*) unless an occupation certificate has been issued in relation to the building or part.

Note: *new building* includes an altered portion of, or an extension to, an existing building.

Note: In circumstance where the works do not relate to occupation the required *occupation certificate* is essentially a certificate of completion of the approved work.

D3 DA715/2006 – 26 Glenmore Road, Paddington – Alterations & additions to existing building & new one bedroom dwelling over gallery – 17/10/2006

Note: The Panel amended the Preamble.

(Bluett/Hatton)

Resolved: Pursuant to Section 80(1) of the Environmental Planning and Assessment Act, 1979

THAT the Council, as the consent authority, grant development consent to Development Application No. 715/2006 for alterations and additions to gallery and first floor dwelling on land at 26 Glenmore Road Paddington, subject to the following conditions:

1. Approved Plans

This consent relates to the work, shown on plans numbered DA01 Rev E dated 28/09/2006, drawn by Indigo Design Group all of which carry a Council stamp "**Approved DA Plans**" and the signature of a Council officer, except where amended by the following conditions.

2. Materials

Details of the colour, texture and substance of all external materials must be submitted to Council or the accredited certifier prior to the issue of a Construction Certificate and are to be to the satisfaction of an authorised Council assessment officer or the accredited certifier. For properties that are located in a Conservation Area or that are Heritage Items, the proposed materials must be to the satisfaction of Council's Heritage Officer.

3. Water conservation

In ensure compliance with Part 5.1.11 of the Paddington Development Control Plan, 1999, the use of low flow water regulators on taps, dual flushing toilets and water saving shower heads shall be incorporated into the design of any new development.

Details shall be submitted with an application for a Construction Certificate.

4. Hours of operation

The hours of operation for the gallery are limited to the following:

Monday to Sunday 10am to 6pm

5. Requirement for a Construction Certificate

In accordance with the provisions of Section 81A of *the Environmental Planning and Assessment Act 1979*, the erection of the building must not be commenced until:

- (a) detailed plans and specifications of the building have been endorsed with a Construction Certificate by:
 - (i) Council; or
 - (ii) an accredited certifier; and
- (b) a principal certifying authority (PCA) has been appointed and the Council has been notified in writing of the appointment, and
- (d) at least two days notice, in writing, has been given to Council of the intention to commence work.

6. Structural adequacy

A statement from a qualified practising Structural Engineer, certifying to the adequacy of the existing structural members, walls and footings to support the additional loads imposed by the proposed development, must be submitted with the Construction Certificate application.

This condition is imposed to ensure the structural integrity of the proposed building work.

7. Structural details

Structural engineering details and design calculations, prepared and certified by a qualified practising Structural Engineer, must be submitted with Construction Certificate application, for all reinforced concrete work, structural steel work, retaining walls, brick fences, shoring and underpinning, isolated piers, chimneys, parapets and other structural members.

This condition is imposed to ensure the structural integrity of the proposed building work.

8. Layout of buildings

The layout of all external walls, including retaining walls and contiguous piling must be checked and verified by survey prior to the commencement of construction to ensure that building construction complies with the development consent and does not encroach beyond the boundaries of the site.

9. Building Inspections

The Applicant, Owner and Builder, jointly and severally, must ensure that they call their Principal Certifying Authority ("the PCA") to carry out such critical phase building inspections required by the PCA, the PCA Service Agreement and that the PCA is satisfied with the level of compliance achieved before the Builder proceeds to the next phase of construction. Ample notice of required inspections must be given to the PCA in accordance with the PCA Service Agreement. The Applicant, Owner and Builder must comply with the PCA Service Agreement (Service Contract) and any lawful direction given by the Principal Certifying Authority.

Note: It is the responsibility of the PCA to ensure that critical phase building inspections are undertaken in accordance with a PCA Service Agreement and issue to the Applicant, Owner and Builder appropriate Notice under Section 109L of the Environmental Planning & Assessment Act 1979 ("the Act") where any breach of this consent occurs. Failure of the PCA to issue such notice may result in Council taking action under Section 109V of the Act.

Failure of the Applicant, Owner and Builder to comply with a PCA Service Agreement and comply with lawful directions of the PCA under this condition may result in Council issuing fines, notices, orders and commencing legal proceedings. Council will only enter into PCA Agreements with the Owner of the land being developed. Council, if appointed as the PCA, will report to the owner of the land being developed.

10. Erosion and sediment control

An erosion and sediment control plan, designed in accordance with the SSROC Soil and Water Management Brochures titled "Do it Right on Site" and the current version of the NSW Landcom publication "Managing Urban Stormwater: Soils and Construction" (*The Blue Book*), must be prepared to show erosion and sediment control measures which are to be installed. The Plan must be submitted to Council or the accredited certifier for approval before commencement of excavation or construction work.

11. Display of Council's warning sign for soil and water management

Throughout the demolition and construction, Council's warning sign for soil and water management must be displayed on the most prominent point of the building site, visible both from the street and site.

A copy of the sign is available from Council.

12. Demolition, excavation and construction hours

Demolition, excavation and construction work must not take place outside the hours of 7.00am to 5.30pm Monday to Friday and 7.00am to 1.00pm Saturday. No work and no deliveries are to take place on Sundays and public holidays. Noise from construction activities associated with the development must comply with the guidelines contained in the NSW EPA *Environmental Noise Control Manual* Chapter 171.

13. Standard for demolition

All demolition work must be undertaken in accordance with the provisions of *Australian Standard AS2601-2001: The Demolition of Structures*.

14. Demolition and disposal of hazardous materials

Removal, cleaning and disposal of lead-based paint must conform to the current EPA guidelines. Demolition of materials incorporating lead is to be conducted in strict accordance with sections 1.5, 1.6, 1.7, 3.1 and 3.9 of the *Australian Standard AS2601-1991, Demolition of Structures*.

Hazardous dust must not be allowed to escape from the site. The use of fine mesh dust proof screens or other measures is recommended. Any existing accumulations of dust (eg. ceiling voids and wall cavities) must be removed by the use of an industrial vacuum cleaner fitted with a high efficiency particulate air (HEPA) filter. All dusty surfaces and dust created from work must be suppressed by a fine water spray. Water must not be allowed to enter the street or stormwater systems. Demolition must not be performed during high winds, which may cause dust to spread beyond the site boundaries.

All contractors and employees directly involved in the removal of hazardous dusts and substances must wear protective equipment conforming to Australian Standard AS1716 Respiratory Protective Devices and must adopt work practices in accordance with the requirements of WorkSafe's *Control of Inorganic Lead At Work* (NOHSC:102(1994) and NOHSC:2015(1994)). All lead-contaminated materials must be disposed of in accordance with the EPA's requirements.

15. Stockpiles

Stockpiles of topsoil, sand, aggregate, soil or other material must not be located on any drainage line or easement, natural watercourse, footpath or roadway, or within the dripline of any Street Tree. Stockpiles within the construction site must be protected with adequate sediment controls, in accordance with Council's Code for Sediment Control.

16. Storage of materials and plant on Council's footpath

Building, excavation or demolition materials and plant must not be stored on Council's footpath and/or roadway unless prior written approval has been obtained from Council's Development Engineer.

17. Location of building operations

Building operations such as brick cutting, washing tools or brushes and mixing mortar must not take place on public roadways or footways or in any other location which could lead to the discharge of materials into the stormwater drainage system.

Footpaths, gutters and roadways must be swept regularly to keep them free from sediment.

18. Temporary disposal of roof water

Stormwater from any roof areas must be linked, via a temporary downpipe, to a Council approved stormwater disposal system immediately upon completion of the roof installation.

19. Site fencing

The site must be appropriately secured and fenced to the satisfaction of Council during demolition, excavation and construction work to ensure there are no unacceptable impacts on the amenity of adjoining properties. Permits for hoardings and or scaffolding on Council land must be obtained and clearly displayed on site.

20. Connection to existing drainage system

Stormwater run-off from the proposed addition must drain to the existing stormwater drainage system.

The existing stormwater drainage pipes on the property affected by the development must be checked and certified by a practising hydraulic engineer to ensure that existing stormwater pipes are in good condition and are operating satisfactorily. Certification and a plan showing pipe locations and diameters must be submitted to the Accredited Certifier prior to the issue of the final Occupation Certificate.

If the existing stormwater pipes are not in good condition and/or not operating satisfactorily, the existing drainage system must be upgraded. Certification and a plan showing pipe locations and diameters of the upgraded system must be submitted to the Accredited Certifier prior to the issue of the final Occupation Certificate.

Stormwater disposal is to comply with the requirements and conditions as set out in Council's Draft Stormwater Drainage Management DCP (Draft Version 1, Public Exhibition Copy dated 23/08/2004). This is available from Council's website <http://www.woollahra.nsw.gov.au>.

Note: connection of stormwater run-off to the Sydney Water sewer system is not permitted.

21. Toilet facilities

- (a) Toilet facilities must be provided, at or in the vicinity of the work site on which work involved in the erection or demolition of a building is being carried out, at the rate of one toilet for every 20 persons or part of 20 persons employed at the site.
- (b) Each toilet provided:
 - (a) must be a standard flushing toilet; and
 - (b) must be connected:
 - (i) to a public sewer; or
 - (ii) if connection to a public sewer is not practicable, to an accredited sewage management facility approved by the Council; or

- (iii) if connection to a public sewer or an accredited sewage management facility is not practicable, to some other sewage management facility approved by the Council.
- (c) The provision of toilet facilities in accordance with this clause must be completed before any other work is commenced.
- (d) In this condition:

accredited sewage management facility means a sewage management facility to which Division 4A of Part 3 of the Local Government (Approvals) Regulation 1993 applies, being a sewage management facility that is installed or constructed to a design or plan the subject of a certificate of accreditation referred to in Clause 95B of the Regulation.

approved by the Council means the subject of an approval in force under Division 1 of Part 3 of the *Local Government (Approvals) Regulation 1993*.

public sewer has the same meaning as it has in the *Local Government (Approvals) Regulation 1993*.

sewage management facility has the same meaning as it has in the Local Government (Approvals) Regulation 1993.

22. Compliance with Building Code of Australia

- (a) All building work must be carried out in accordance with the provisions of the *Building Code of Australia*.
- (c) This condition does not apply to the extent to which an exemption is in force under Clause 187 or 188, of the *Environmental Planning and Assessment Regulation 2000*, subject to the terms of any condition or requirement referred to in Clause 187 (6) or 188 (4) of the Regulation.

23. Signs to be erected on building and demolition sites

- (a) A sign must be erected in a prominent position on any work site on which work involved in the erection or demolition of a building is being carried out:
 - (i) stating that unauthorised entry to the work site is prohibited; and
 - (ii) showing the name of the person in charge of the work site and a telephone number at which that person may be contacted outside working hours.
- (b) Any such sign must be removed when the work has been completed.
- (c) This clause does not apply to:
 - (i) building work carried out inside an existing building; or
 - (ii) building work carried out on premises that must be occupied continuously (both during and outside working hours) while the work is being carried out.

24. Support for neighbouring buildings

- (a) If an excavation associated with the erection or demolition of a building extends below the level of the base of the footings of a building on an adjoining allotment of land, the person causing the excavation to be made:
- (i) must preserve and protect the building from damage; and
 - (ii) if necessary, must underpin and support the building in an approved manner; and
 - (iii) must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.
- (b) The owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this condition, whether carried out on the allotment of land being excavated or on the adjoining allotment of land.

In this condition, allotment of land includes a public road and any other public place.

25. Residential building work

- (a) Building work that involves residential building work (within the meaning of the *Home Building Act 1989*) must not be carried out unless the principal certifying authority (PCA) for the development to which the work relates:
- in the case of work to be done by a licensee under that Act:
 - (i) has been informed in writing of the licensee's name and contractor license number; and
 - (ii) is satisfied that the licensee has complied with the requirements of Part 6 of that Act; or
 - in the case of work to be done by any other person:
 - (iii) has been informed in writing of the person's name and owner-builder permit number; or
 - (iv) has been given a declaration, signed by the owner of the land, that states that the reasonable market cost of the labour and materials involved in the work is less than the amount prescribed for the purposes of the definition of owner-builder work in Section 29 of that Act,

and is given appropriate information and declarations under paragraphs (a) and (b) whenever arrangements for the doing of the work are changed in such a manner as to render out of date any information or declaration previously given under either of those paragraphs.

Note: The amount referred to in paragraph (a) (iv) above is prescribed by regulations under the *Home Building Act 1989*. As at the date on which this Regulation was Gazetted, that amount was \$5,000. As those regulations are amended from time to time, so that amount may vary.

- (b) A certificate purporting to be issued by an approved insurer under Part 6 of the *Home Building Act 1989* that states that a person is the holder of an insurance policy issued for the purposes of that Part is, for the purposes of this clause, sufficient evidence that the person has complied with the requirements of that Part.

26. Residential building work over \$12,000 in value

Council must be provided with the following information prior to the commencement of any works;

- (a) the proposed builder's details (in writing); and
- (b) proof of payment of the required insurance premium pursuant to Part 6 of the *Home Building Act 1989*.

27. Payment of Long Service Levy, Security, Development Levy and Fees (G.1)

The person(s) with the benefit of this consent must pay the following long service levy, security, development levy, and fees prior to the issue of any *construction certificate*, *subdivision certificate* or *occupation certificate*, as will apply.

The *certifying authority* must not issue any *Part 4A Certificate* until provided with the original receipt(s) for the payment of all of the following levy, security, contributions, and fees. Specifically

- d) prior to the issue of a *construction certificate*, where a construction certificate is required; or
- e) prior to the issue of a *subdivision certificate*, where only a subdivision certificate is required; or
- f) prior to the issue of an *occupation certificate* in any other instance.

Description	Amount	Indexed	Council Fee Code
LONG SERVICE LEVY under Building and Construction Industry Long Service Payments Act 1986			
Long Service Levy (Currently 0.35% of contract value – subject to change. Contact LSL Corporation to confirm current rate)	Contact LSL Corporation	No	
SECURITY under section 80A(6) of the Environmental Planning and Assessment Act 1979			
Property Damage Security Deposit - Making good any damage caused to any property of the Council as a consequence of the doing of anything to which the consent relates.	\$4 600	Yes, yearly	T600
DEVELOPMENT LEVY under Woollahra Section 94A Development Contributions Plan 2005 This plan may be inspected at Woollahra Council or downloaded from our website www.woollahra.nsw.gov.au .			
Development Levy	\$620	Yes, quarterly	T94
INSPECTION FEES under section 608 of the Local Government Act 1993			
Security Administration Fee	\$163	No	T16
TOTAL SECURITY, CONTRIBUTIONS, LEVIES AND FEES	\$5 383 Plus any relevant indexed amounts and long service levy		

How must the payments be made?

Payments must be made by:

1. Cash deposit with Council,
2. Credit card payment with Council, or
3. Bank cheque made payable to Woollahra Municipal Council.

The payment of a security may be made by a bank guarantee where:

- a) the guarantee is by an Australian bank for the amount of the total outstanding contribution;
- b) the bank unconditionally agrees to pay the guaranteed sum to the Council on written request by Council on completion of the development or no earlier than 12 months from the provision of the guarantee whichever occurs first;
- c) the bank agrees to pay the guaranteed sum without reference to the applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent; and
- d) the bank's obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required.

How will a security and a section 94A levy be indexed?

To ensure that the value of a security and development levy are not eroded over time by increases in costs, the security and proposed cost of carrying out development (from which the development levy is calculated) will be indexed either annually or quarterly (see table above). Clause 3.13 of the Woollahra Section 94A Development Contributions Plan 2005 sets out the formula and index to be used in adjusting the s.94A levy.

Do you need HELP indexing the security, bond or levy?

Please contact our customer service officers. Failure to correctly calculate the adjusted security, bond or development levy will delay the issue of any Part 4A Certificate and could void any Part 4A Certificate (construction certificate, subdivision certificate, or occupation certificate).

Deferred periodic payment of section 94A levy under the Woollahra Section 94A Development Contributions Plan 2005

Where the applicant makes a written request supported by reasons for payment of the section 94A levy other than as required by clause 3.9, the Council may accept deferred or periodic payment. The decision to accept a deferred or periodic payment is at the sole discretion of the Council, which will consider:

- a) the reasons given;
- b) whether any prejudice will be caused to the community deriving benefit from the public facilities;
- c) whether any prejudice will be caused to the efficacy and operation of this plan; and
- d) whether the provision of public facilities in accordance with the adopted works schedule will be adversely affected.

Council may, as a condition of accepting deferred or periodic payment, require the provision of a bank guarantee where:

- a) the guarantee is by an Australian bank for the amount of the total outstanding contribution;
- b) the bank unconditionally agrees to pay the guaranteed sum to the Council on written request by Council on completion of the development or no earlier than 12 months from the provision of the guarantee whichever occurs first;
- c) the bank agrees to pay the guaranteed sum without reference to the applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent; and
- d) the bank's obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required.

Any deferred or outstanding component of the section 94A levy will be adjusted in accordance with clause 3.13 of the plan. The applicant will be required to pay any charges associated with establishing or operating the bank guarantee. Council will not cancel the bank guarantee until the outstanding contribution as indexed and any accrued charges are paid.

28. Occupation of premises

A person must not commence occupation or use of the whole or any part of a *new building* (within the meaning of section 109H (4) of the *Act*) unless an occupation certificate has been issued in relation to the building or part.

Note: *new building* includes an altered portion of, or an extension to, an existing building.

Note: In circumstance where the works do not relate to occupation the required *occupation certificate* is essentially a certificate of completion of the approved work.

D4 DA646/2006 – 21 Spencer Street, Rose Bay – Alterations and additions – 27/9/2006

Note: Late correspondence from Mr B Anderson the Applicant, dated 25 February 2007, was noted.

Note: Mr B Anderson the Applicant, addressed the Panel.

Note: The Panel added 3 new conditions Nos. 29 (Structural adequacy), 30 (Structural details) and 31 (Layout of buildings) and deleted original Condition No. 5 (Modification of details of the development (s80A(1)(g) of the Act))

(Hatton/Bluett)

Resolved: Pursuant to Section 80(1) of the Environmental Planning and Assessment Act, 1979

THAT the Council, as the consent authority, grant development consent to DA 646/2006/1 for alterations and additions to an existing two-storey dwelling, including a new double-width carport at the front of the dwelling, on land at 21 Spencer Street, Rose Bay, subject to the following conditions:

1. Approved Plans

The development must be carried out in accordance with plans numbered 1160/DA01 and 1160/DA02 Revision B, dated 31 January 2007, drawn by Sulcor Holdings Pty Ltd, all of which carry a Council stamp "**Approved DA Plans**" and the signature of a Council officer, except where amended by the following conditions.

2. Requirement for a Construction Certificate

In accordance with the provisions of Section 81A of the *Environmental Planning and Assessment Act 1979*, the erection of the building must not be commenced until:

- (a) detailed plans and specifications of the building have been endorsed with a Construction Certificate by:
 - (i) Council; or
 - (ii) an accredited certifier; and

- (b) a principal certifying authority (PCA) has been appointed and the Council has been notified in writing of the appointment, and
- (c) at least two days notice, in writing, has been given to Council of the intention to commence work.

3. Materials

Details of the colour, texture and substance of all external materials must be submitted to Council or the accredited certifier prior to the issue of a Construction Certificate and are to be to the satisfaction of an authorised Council assessment officer or the accredited certifier. For properties that are located in a Conservation Area or that are Heritage Items, the proposed materials must be to the satisfaction of Council's Heritage Officer.

4. Drawings to show levels and heights

The reduced levels of the ground floor, first floor and the overall height of the roof in relation to Australian Height Datum must be shown on the drawings submitted with the Construction Certificate Application to ensure that building construction complies with the development consent.

5. Demolition, excavation and construction hours

Demolition, excavation and construction work must not take place outside the hours of 7.00am to 5.30pm Monday to Friday and 7.00am to 1.00pm Saturday. No work and no deliveries are to take place on Sundays and public holidays. Noise from construction activities associated with the development must comply with the guidelines contained in the NSW EPA *Environmental Noise Control Manual* Chapter 171.

6. Machine excavation

Excavation or removal of any materials involving the use of machinery of any kind, including compressors and jack hammers, must be limited to between 9.00am and 4.00 pm Mondays to Fridays, with regular breaks of 15 minutes each hour. This condition is imposed to ensure reasonable standards of amenity for occupants of neighbouring properties.

7. Building Inspections

The Applicant, Owner and Builder, jointly and severally, must ensure that they call their Principal Certifying Authority ("the PCA") to carry out such critical phase building inspections required by the PCA, the PCA Service Agreement and that the PCA is satisfied with the level of compliance achieved before the Builder proceeds to the next phase of construction. Ample notice of required inspections must be given to the PCA in accordance with the PCA Service Agreement. The Applicant, Owner and Builder must comply with the PCA Service Agreement (Service Contract) and any lawful direction given by the Principal Certifying Authority.

Note: It is the responsibility of the PCA to ensure that critical phase building inspections are undertaken in accordance with a PCA Service Agreement and issue to the Applicant, Owner and Builder appropriate Notice under Section 109L of the Environmental Planning & Assessment Act 1979 ("the Act") where any breach of this consent occurs. Failure of the PCA to issue such notice may result in Council taking action under Section 109V of the Act. Failure of the Applicant, Owner and Builder to comply with a PCA Service Agreement and comply with lawful directions of the PCA under this condition may result in Council issuing fines, notices, orders and commencing legal proceedings. Council will only enter into PCA Agreements with the Owner of the land being developed. Council, if appointed as the PCA, will report to the owner of the land being developed.

8. Tree Protection Zones

To limit the potential for damage to trees to be retained, Tree Protection Zones are to be established for all trees to be retained on site. The Tree Protection Zones are to comply with the following requirements:

- a) Tree Protection Zones are to be established within the specified radius from the trunks of the following trees;

Council Reference No:	Species	Location	Radius from Trunk (Metres)
1	<i>Lophostemon confertus</i> (Brush Box)	Council road reserve at front of 23 Spencer street	5

- b) Tree Protection Zones are to be fenced with a 1.8 meter high chainmesh or weldmesh fence to minimise disturbance to existing ground conditions. The area within the fence must be mulched, to a depth of 75mm, irrigated and maintained for the duration of the construction works.
- d) Installation of all Tree Protection measures is to be at the direction of and overseen by a qualified Arborist (minimum Australian Qualification Framework Level 4 or recognised equivalent).
- e) A sign must be erected on each side of the fence indicating the existence of a Tree Protection Zone and providing the contact details of the site Arborist.
- f) Existing soil levels must be maintained within Tree Protection Zones. Where excavation is undertaken adjacent such an area, the edge of the excavation must be stabilised, until such time as permanent measures are installed (eg. retaining wall etc) to prevent erosion within the Tree Protection Zone.
- g) Sediment control measures are to be installed around all Tree Protection Zones to protect the existing soil levels.
- h) The storage of materials, stockpiling, siting of works sheds, preparation of mixes, cleaning of tools or equipment is not permitted within Tree Protection Zones.

Site personnel must be made aware of all Tree Protection requirements, measures and any actions that constitute a breach of the Conditions of Development Consent with regard to tree protection on site during their site induction.

9. Trees which may be removed

This consent includes approval under Council's Tree Preservation Order to remove the following trees:

Council Reference No:	Species	Location
1	Mandarin tree	Rear of dwelling adjacent to the southern boundary

The Construction Certificate plans must include reference to the removal of the above mentioned trees and identify the trees by Council's reference number (Council Ref No:) and colour or shade them in the colour red.

10. Replacement trees which must be planted

The following compensatory replacement plantings must be planted to ensure the preservation of the landscape character of the area.

Species/Type	Planting Location	Container Size or Size of Tree (@ time of planting)	Minimum Dimensions at Maturity
Murraya paniculata	Rear of dwelling adjacent to the southern boundary	50 litres for each plant	3m

11. Stormwater disposal

Stormwater must be disposed of by an appropriate method specified in Council's Draft Stormwater Development Control Plan and Local Approvals Policy. Details of the proposed method/s of disposal must be submitted with the Construction Certificate Application.

12. Connection to existing drainage system

Stormwater run-off from the proposed additions and paved areas must drain to the existing stormwater drainage system.

The existing stormwater drainage pipes on the property affected by the development must be checked and certified by a practising hydraulic engineer to ensure that existing stormwater pipes are in good condition and are operating satisfactorily. Certification and a plan showing pipe locations and diameters must be submitted to the Accredited Certifier prior to the issue of the final Occupation Certificate.

If the existing stormwater pipes are not in good condition and/or not operating satisfactorily, the existing drainage system must be upgraded. Certification and a plan showing pipe locations and diameters of the upgraded system must be submitted to the Accredited Certifier prior to the issue of the final Occupation Certificate.

Stormwater disposal is to comply with the requirements and conditions as set out in Council's Draft Stormwater Drainage Management DCP (Draft Version 1, Public Exhibition Copy dated 23/08/2004). This is available from Council's website <http://www.woollahra.nsw.gov.au>.

Note: connection of stormwater run-off to the Sydney Water sewer system is not permitted.

13. Payment of Long Service Levy, Security, Development Levy and Fees

The person(s) with the benefit of this consent must pay the following long service levy, security, development levy, and fees prior to the issue of any *construction certificate*, *subdivision certificate* or *occupation certificate*, as will apply.

The *certifying authority* must not issue any *Part 4A Certificate* until provided with the original receipt(s) for the payment of all of the following levy, security, contributions, and fees. Specifically;

- a) prior to the issue of a *construction certificate*, where a construction certificate is required; or
- b) prior to the issue of a *subdivision certificate*, where only a subdivision certificate is required; or
- c) prior to the issue of an *occupation certificate* in any other instance.

Description	Amount	Indexed	Council Fee Code
LONG SERVICE LEVY under Building and Construction Industry Long Service Payments Act 1986			
Long Service Levy Use Calculator: http://www.lspc.nsw.gov.au/levy_information/?levy_information/levy_calculator.stm	Contact LSL Corporation or use their online calculator	No	
SECURITY under section 80A(6) of the Environmental Planning and Assessment Act 1979			
Property Damage Security Deposit - Making good any damage caused to any property of the Council as a consequence of the doing of anything to which the consent relates.	\$6,000.00	No	T600
DEVELOPMENT LEVY under Woollahra Section 94A Development Contributions Plan 2005 This plan may be inspected at Woollahra Council or downloaded from our website www.woollahra.nsw.gov.au .			
Development Levy	\$2,000.00 + Index Amount	Yes, quarterly	T94
INSPECTION FEES under section 608 of the Local Government Act 1993			
Security Administration Fee	\$163	No	T16
TOTAL SECURITY, CONTRIBUTIONS, LEVIES AND FEES	\$8,163.00 Plus any relevant indexed amounts and long service levy		

How must the payments be made?

Payments must be made by:

1. Cash deposit with Council,
2. Credit card payment with Council, or
3. Bank cheque made payable to Woollahra Municipal Council.

The payment of a security may be made by a bank guarantee where:

- a) the guarantee is by an Australian bank for the amount of the total outstanding contribution;

- b) the bank unconditionally agrees to pay the guaranteed sum to the Council on written request by Council on completion of the development or no earlier than 12 months from the provision of the guarantee whichever occurs first;
- c) the bank agrees to pay the guaranteed sum without reference to the applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent; and
- d) the bank's obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required.

How will the section 94A levy be indexed?

To ensure that the value of the development levy is not eroded over time by increases in costs, the proposed cost of carrying out development (from which the development levy is calculated) will be indexed either annually or quarterly (see table above). Clause 3.13 of the Woollahra Section 94A Development Contributions Plan 2005 sets out the formula and index to be used in adjusting the s.94A levy.

Do you need HELP indexing the levy?

Please contact our customer service officers. Failure to correctly calculate the development levy will delay the issue of any Part 4A Certificate and could void any Part 4A Certificate (construction certificate, subdivision certificate, or occupation certificate).

Deferred periodic payment of section 94A levy under the Woollahra Section 94A Development Contributions Plan 2005

Where the applicant makes a written request supported by reasons for payment of the section 94A levy other than as required by clause 3.9, the Council may accept deferred or periodic payment. The decision to accept a deferred or periodic payment is at the sole discretion of the Council, which will consider:

- a) the reasons given;
- b) whether any prejudice will be caused to the community deriving benefit from the public facilities;
- c) whether any prejudice will be caused to the efficacy and operation of this plan; and
- d) whether the provision of public facilities in accordance with the adopted works schedule will be adversely affected.

Council may, as a condition of accepting deferred or periodic payment, require the provision of a bank guarantee where:

- a) the guarantee is by an Australian bank for the amount of the total outstanding contribution;
- b) the bank unconditionally agrees to pay the guaranteed sum to the Council on written request by Council on completion of the development or no earlier than 12 months from the provision of the guarantee whichever occurs first;
- c) the bank agrees to pay the guaranteed sum without reference to the applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent; and
- d) the bank's obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required.

Any deferred or outstanding component of the section 94A levy will be adjusted in accordance with clause 3.13 of the plan. The applicant will be required to pay any charges associated with establishing or operating the bank guarantee. Council will not cancel the bank guarantee until the outstanding contribution as indexed and any accrued charges are paid.

14. Erosion and sediment control

Erosion and sediment controls, designed in accordance with the SSROC Soil and Water Management Brochure and the NSW Environmental Protection Authority's *Managing Urban Stormwater: Construction Activities*, must be implemented during demolition, excavation and construction of the development. All controls must be maintained at all times.

15. Stockpiles

Stockpiles of topsoil, sand, aggregate, soil or other material must not be located on any drainage line or easement, natural watercourse, footpath or roadway, or within the dripline of any Street Tree. Stockpiles within the construction site must be protected with adequate sediment controls, in accordance with Council's Code for Sediment Control.

16. Location of building operations

Building operations such as brick cutting, washing tools or brushes and mixing mortar must not take place on public roadways or footways or in any other location which could lead to the discharge of materials into the stormwater drainage system.

Footpaths, gutters and roadways must be swept regularly to keep them free from sediment.

17. Temporary disposal of roof water

Stormwater from any roof areas must be linked, via a temporary downpipe, to a Council approved stormwater disposal system immediately upon completion of the roof installation.

18. Standard for demolition

All demolition work must be undertaken in accordance with the provisions of *Australian Standard AS2601-2001: The Demolition of Structures*.

19. Site fencing

The site must be appropriately secured and fenced to the satisfaction of Council during demolition, excavation and construction work to ensure there are no unacceptable impacts on the amenity of adjoining properties. Permits for hoardings and or scaffolding on Council land must be obtained and clearly displayed on site.

20. Protection of services

Prior to any excavation works, the location and depth of all services (telephone, cable TV, electricity, gas, water, sewer, drainage, etc.) must be ascertained. The developer must meet all costs of any adjustment, relocation or reinstatement of any services.

21. Storage of materials and plant on Council's footpath

Building, excavation or demolition materials and plant must not be stored on Council's footpath and/or roadway unless prior written approval has been obtained from Council's Development Engineer.

22. Repair of Damaged Infrastructure

If Council's infrastructure is damaged during the course of works, Council's Development Engineer must be notified and necessary repairs must be undertaken within the time stipulated by Council, to Council's specifications, and at no cost to Council. Works generally must be in accordance with the relevant clauses of the current edition of AUS-SPEC.

If work is not undertaken to the satisfaction of the Development Engineer with regard to time or quality, Council may carry out remedial works and deduct the cost from the Damage Security Deposit.

23. Compliance with Building Code of Australia

- (a) All building work must be carried out in accordance with the provisions of the *Building Code of Australia*.
- (b) This condition does not apply to the extent to which an exemption is in force under Clause 187 or 188, of the *Environmental Planning and Assessment Regulation 2000*, subject to the terms of any condition or requirement referred to in Clause 187 (6) or 188 (4) of the Regulation.

24. Residential building work

- (a) Building work that involves residential building work (within the meaning of the *Home Building Act 1989*) must not be carried out unless the principal certifying authority (PCA) for the development to which the work relates:
 - in the case of work to be done by a licensee under that Act:
 - (i) has been informed in writing of the licensee's name and contractor license number; and
 - (ii) is satisfied that the licensee has complied with the requirements of Part 6 of that Act; or
 - in the case of work to be done by any other person:
 - (iii) has been informed in writing of the person's name and owner-builder permit number; or
 - (iv) has been given a declaration, signed by the owner of the land, that states that the reasonable market cost of the labour and materials involved in the work is less than the amount prescribed for the purposes of the definition of owner-builder work in Section 29 of that Act,

and is given appropriate information and declarations under paragraphs (a) and (b) whenever arrangements for the doing of the work are changed in such a manner as to render out of date any information or declaration previously given under either of those paragraphs.

Note: The amount referred to in paragraph (a) (iv) above is prescribed by regulations under the *Home Building Act 1989*. As at the date on which this Regulation was Gazetted, that amount was \$5,000. As those regulations are amended from time to time, so that amount may vary.

- (b) A certificate purporting to be issued by an approved insurer under Part 6 of the *Home Building Act 1989* that states that a person is the holder of an insurance policy issued for the purposes of that Part is, for the purposes of this clause, sufficient evidence that the person has complied with the requirements of that Part.

25. Excavations and backfilling

- (a) All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with appropriate professional standards.
- (b) All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.

26. Support for neighbouring buildings

- (a) If an excavation associated with the erection or demolition of a building extends below the level of the base of the footings of a building on an adjoining allotment of land, the person causing the excavation to be made:
 - (i) must preserve and protect the building from damage; and
 - (ii) if necessary, must underpin and support the building in an approved manner; and
 - (iii) must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.
- (b) The owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this condition, whether carried out on the allotment of land being excavated or on the adjoining allotment of land.
- (c) In this condition, allotment of land includes a public road and any other public place.

27. Signs to be erected on building and demolition sites

- (a) A sign must be erected in a prominent position on any work site on which work involved in the erection or demolition of a building is being carried out:
 - (i) stating that unauthorised entry to the work site is prohibited; and
 - (ii) showing the name of the person in charge of the work site and a telephone number at which that person may be contacted outside working hours.
- (b) Any such sign must be removed when the work has been completed.
- (c) This clause does not apply to:
 - (i) building work carried out inside an existing building; or
 - (ii) building work carried out on premises that must be occupied continuously (both during and outside working hours) while the work is being carried out.

28. Residential building work over \$12,000 in value

Council must be provided with the following information prior to the commencement of any works:

- (a) the proposed builder's details (in writing); and
- (b) proof of payment of the required insurance premium pursuant to Part 6 of the *Home Building Act 1989*.

29. Structural adequacy

A statement from a qualified practising Structural Engineer, certifying to the adequacy of the existing structural members, walls and footings to support the additional loads imposed by the proposed development, must be submitted with the Construction Certificate application.

This condition is imposed to ensure the structural integrity of the proposed building work.

30. Structural details

Structural engineering details and design calculations, prepared and certified by a qualified practising Structural Engineer, must be submitted with Construction Certificate application, for all reinforced concrete work, structural steel work, retaining walls, brick fences, shoring and underpinning, isolated piers, chimneys, parapets and other structural members.

This condition is imposed to ensure the structural integrity of the proposed building work.

31. Layout of buildings

The layout of all external walls, including retaining walls and contiguous piling must be checked and verified by survey prior to the commencement of construction to ensure that building construction complies with the development consent and does not encroach beyond the boundaries of the site.

D5 DA601/2006 – 335 & 337 Edgecliff Road, Woollahra – New double garage with timber deck over – 15/9/2006

Note: Late correspondence from Mr D Sunman on behalf of the Objectors, dated 27 February 2007, was noted.

Note: Ms J Brain an Objector of 337A Edgecliff Road, Woollahra, Ms D Fairly an Objector of 337B Edgecliff Road, Woollahra and Mr A De La Vega, the Applicant, addressed the Panel.

Note: The Panel amended Condition No. C.1 (Modification of details of the development (s80A(1)(g) of the Act)).

(Hatton/Bluett)

Resolved: Pursuant to Section 80(1) of the Environmental Planning and Assessment Act, 1979

THAT the Council, as the consent authority, grant development consent to Development Application 601/2006 for a new double garage with timber deck over on land at 335 Edgecliff Road, Woollahra and the demolition of a section of wall and installation of a traffic mirror on land at 337 Edgecliff Road, Woollahra subject to the following conditions:

A. General Conditions

A.1 Conditions

Consent is granted subject to the following conditions imposed pursuant to section 80 of the Environmental Planning & Assessment Act 1979 (“the *Act*”) and the provisions of the Environmental Planning and Assessment Regulation 2000 (“the *Regulation*”) such conditions being reasonable and relevant to the development as assessed pursuant to section 79C of the Act.

A.2 Definitions

Unless specified otherwise words have the same meaning as defined by the *Act*, the *Regulation* and the *Interpretation Act 1987* as in force at the date of consent.

Applicant means the applicant for this Consent.

Approved Plans mean the plans endorsed by Council referenced by this consent as amended by conditions of this consent.

AS or *AS/NZS* means Australian Standard® or Australian/New Zealand Standard®, respectively, published by Standards Australia International Limited.

BCA means the Building Code of Australia as published by the Australian Building Codes Board as in force at the date of issue of any *Construction Certificate*.

Council means Woollahra Municipal Council

Court means the Land and Environment Court

Local native plants means species of native plant endemic to Sydney’s eastern suburbs (see the brochure titled “Local Native Plants for Sydney’s Eastern Suburbs published by the Southern Sydney Regional Organisation of Councils).

Stormwater Drainage System means all works, facilities and documentation relating to:

- a) The collection of stormwater,
- b) The retention of stormwater,
- c) The reuse of stormwater,
- d) The detention of stormwater,
- e) The controlled release of stormwater; and
- f) Connections to easements and public stormwater systems.

Owner means the owner of the *site* and successors in title to the *site*.

Owner Builder has the same meaning as in the *Home Building Act 1989*.

PCA means the *Principal Certifying Authority* under the *Act*.

Principal Contractor has the same meaning as in the *Act* or where a *principal contractor* has not been appointed by the *owner* of the land being developed *Principal Contractor* means the *owner* of the land being developed.

Professional Engineer has the same meaning as in the *BCA*.

Public Place has the same meaning as in the *Local Government Act 1993*.

Road has the same mean as in the *Roads Act 1993*.

SEE means the final version of the Statement of Environmental Effects lodged by the *Applicant*.

Site means the land being developed subject to this consent.

WLEP 1995 means *Woollahra Local Environmental Plan 1995*

Work for the purposes of this consent means:

- a) the use of land in connection with development,
- b) the subdivision of land,
- c) the erection of a building,
- d) the carrying out of any work,
- e) the use of any site crane, machine, article, material, or thing,
- f) the storage of waste, materials, site crane, machine, article, material, or thing,
- g) the demolition of a building,
- h) the piling, piercing, cutting, boring, drilling, rock breaking, rock sawing or excavation of land,
- i) the delivery to or removal from the *site* of any machine, article, material, or thing, or
- j) the occupation of the *site* by any person unless authorised by an *occupation certificate*.

Note: Interpretation of Conditions - Where there is any need to obtain an interpretation of the intent of any condition this must be done in writing to Council and confirmed in writing by Council.

A.3 Approved Plans and supporting documents

Those with the benefit of this consent must carry out all work and maintain the use and works in accordance with the plans and supporting documents listed below as submitted by the Applicant and to which is affixed a Council stamp "Approved DA Plans" **unless modified by any following condition**. Where the plans relate to alterations or additions only those works shown in colour or highlighted are approved.

Reference	Description	Author/Drawn	Date(s)
DA003, DA005 (1/2), DA005 (2/2), DA006	Architectural Plans	De La Vega Architects	Dated September 2006
DA002	Architectural Plans	De La Vega Architects	Received by Council's records department on the 31 January 2007.

Note: Warning to Accredited Certifiers – You should always insist on sighting the original Council stamped approved plans. You should not rely solely upon the plan reference numbers in this condition. Should the applicant not be able to provide you with the original copy Council will provide you with access to its files so you may review our original copy of the approved plan.

Note: These plans and supporting documentation may be subject to conditions imposed under section 80A(1)(g) of the *Act* modifying or amending the development (refer to conditions which must be satisfied prior to the issue of any *Construction Certificate*.)

A.4 Prescribed Conditions

Prescribed conditions in force under the *Act* and *Regulation* must be complied with.

Note: It is the responsibility of those acting with the benefit of this consent to comply with all prescribed conditions under the *Act* and the *Regulation*. Free access can be obtained to all NSW legislation at www.legislation.nsw.gov.au

B. Conditions which must be satisfied prior to the demolition of any building or construction

B.1 Construction Management

A construction management plan must be submitted for the approval of Council's Development Engineer before the commencement of demolition, excavation or construction works. The plan must:-

- 1. describe the anticipated impact of the construction works on:**
 - local traffic routes
 - pedestrian circulation adjacent to the building site
 - and on-street parking in the local area, and;
- 2. describe the means proposed to:**
 - manage construction works to minimise such impacts,
 - provide for the standing of vehicles during construction,
 - provide for the movement of trucks to and from the site, and deliveries to the site, and;
- 3. show the location of:**
 - any site sheds and any anticipated use of cranes and concrete pumps,
 - any areas of Council property on which it is proposed to install a Works Zone (Construction Zone),
 - structures to be erected such as hoardings, scaffolding or shoring,
 - any excavation.

The Plan must make provision for all materials, plant, etc. to be stored within the development site at all times during construction. Structures or works on Council property such as hoardings, scaffolding, shoring or excavation need separate approval from Council. Standing of cranes and concrete pumps on Council property will need approval on each occasion.

Note: A minimum of eight weeks will be required for assessment. Work must not commence until the Construction Management Plan is approved. Failure to comply with this condition may result in fines and proceedings to stop work.

C. Conditions which must be satisfied prior to the issue of any construction certificate

C.1 Modification of details of the development (s80A(1)(g) of the Act)

The *approved plans* must be amended and the *Construction Certificate* plans and specification, required to be submitted to the *Certifying Authority* pursuant to clause 139 of the *Regulation*, must detail:

- a) All reference to use of lower level for garaging of vehicles is to be removed from the plans.

- b) This application approves the traffic mirror and demolition of the section of concrete wall/curbing as shown on the approved plans. No other works are approved outside the title boundaries of the subject site.

Any proposed structural works to the common driveway shall be the subject of a further Development Application.

Note: The effect of this condition is that it requires design changes and/or further information to be provided with the *Construction Certificate* drawings and specifications to address specific issues identified during assessment under section 79C of the *Act*.

Note: Clause 146 of the *Regulation* prohibits the issue of any *Construction Certificate* subject to this condition unless the *Certifying Authority* is satisfied that the condition has been complied with.

Note: Clause 145 of the *Regulation* prohibits the issue of any *Construction Certificate* that is inconsistent with this consent.

C.2 Payment of Security, Levies and Fees (S80A(6) & S94 of the Act, Section 608 of the Local Government Act 1993)

The person(s) with the benefit of this consent must pay the following long service levy, security, development levy, and fees prior to the issue of any *construction certificate*, *subdivision certificate* or *occupation certificate*, as will apply.

The *certifying authority* must not issue any *Part 4A Certificate* until provided with the original receipt(s) for the payment of all of the following levy, security, contributions, and fees. Specifically

- a) prior to the issue of a *construction certificate*, where a construction certificate is required; or
- b) prior to the issue of a *subdivision certificate*, where only a subdivision certificate is required; or
- c) prior to the issue of an *occupation certificate* in any other instance.

Description	Amount	Indexed	Council Fee Code
LONG SERVICE LEVY under Building and Construction Industry Long Service Payments Act 1986			
Long Service Levy Use Calculator: http://www.lspc.nsw.gov.au/levy_information/?levy_information/levy_calculator.stm	Contact LSL Corporation or use their online calculator	No	
SECURITY under section 80A(6) of the Environmental Planning and Assessment Act 1979			
Property Damage Security Deposit - Making good any damage caused to any property of the <i>Council</i> as a consequence of the doing of anything to which the consent relates.	\$2000.00	No	T600
INSPECTION FEES under section 608 of the Local Government Act 1993			
Security Administration Fee	\$163.00	No	T16
TOTAL SECURITY, CONTRIBUTIONS, LEVIES AND FEES	\$2163.00 Plus any relevant indexed amounts and long service levy		

Building & Construction Industry Long Service Payment

The Long Service Levy under Section 34 of the *Building & Construction Industry Long Service Payment Act, 1986*, must be paid and proof of payment provided to the *Certifying Authority* prior to the issue of any *Construction Certificate*.

Note: The Levy can be paid directly to the Long Services Payments Corporation or to Council. Further information can be obtained from the Long Service Payments Corporation's website <http://www.lspc.nsw.gov.au/> or by telephoning the Long Service Payments Corporation on 13 14 41.

How must the payments be made?

Payments must be made by:

1. Cash deposit with Council,
2. Credit card payment with Council, or
3. Bank cheque made payable to Woollahra Municipal Council.

The payment of a security may be made by a bank guarantee where:

- a) the guarantee is by an Australian bank for the amount of the total outstanding contribution;
- b) the bank unconditionally agrees to pay the guaranteed sum to the Council on written request by Council on completion of the development or no earlier than 12 months from the provision of the guarantee whichever occurs first;
- c) the bank agrees to pay the guaranteed sum without reference to the applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent; and
- d) the bank's obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required.

How will the section 94A levy be indexed?

To ensure that the value the development levy is not eroded over time by increases in costs, the proposed cost of carrying out development (from which the development levy is calculated) will be indexed either annually or quarterly (see table above). Clause 3.13 of the Woollahra Section 94A Development Contributions Plan 2005 sets out the formula and index to be used in adjusting the s.94A levy.

Do you need HELP indexing the levy?

Please contact our customer service officers. Failure to correctly calculate the adjusted the development levy will delay the issue of any Part 4A Certificate and could void any Part 4A Certificate (construction certificate, subdivision certificate, or occupation certificate).

Deferred periodic payment of section 94A levy under the Woollahra Section 94A Development Contributions Plan 2005

Where the applicant makes a written request supported by reasons for payment of the section 94A levy other than as required by clause 3.9, the Council may accept deferred or periodic payment. The decision to accept a deferred or periodic payment is at the sole discretion of the Council, which will consider:

- a) the reasons given;
- b) whether any prejudice will be caused to the community deriving benefit from the public facilities;
- c) whether any prejudice will be caused to the efficacy and operation of this plan; and
- d) whether the provision of public facilities in accordance with the adopted works schedule will be adversely affected.

Council may, as a condition of accepting deferred or periodic payment, require the provision of a bank guarantee where:

- a) the guarantee is by an Australian bank for the amount of the total outstanding contribution;
- b) the bank unconditionally agrees to pay the guaranteed sum to the Council on written request by Council on completion of the development or no earlier than 12 months from the provision of the guarantee whichever occurs first;
- c) the bank agrees to pay the guaranteed sum without reference to the applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent; and
- d) the bank's obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required.

Any deferred or outstanding component of the section 94A levy will be adjusted in accordance with clause 3.13 of the plan. The applicant will be required to pay any charges associated with establishing or operating the bank guarantee. Council will not cancel the bank guarantee until the outstanding contribution as indexed and any accrued charges are paid.

C.3 Damage security deposit

A security deposit of **\$2,000 (Two thousand dollars)** for the cost of making good any damage to Council property caused as a consequence of the construction work, plus an administration fee of **\$163.00**, must be paid to Council prior to the issue of the Construction Certificate. The security deposit, which may be in the form of a bank guarantee, has been calculated in accordance with the following schedule.

Estimated cost of work	Deposit
Works up to \$50,000	\$2,000
Works in excess of \$50,000 & up to \$100,000	\$4,000
Works in excess of \$100,000	\$4,000+\$200/\$10,000 estimated cost>\$100,000

Council may use all or part of the Damage Security Deposit to complete damage restoration works if they do not meet Council's requirements.

C.4 Structural Adequacy of Existing Supporting Structures

A certificate from a *professional engineer* (Structural Engineer), certifying the adequacy of the existing supporting structure to support the additional loads proposed to be imposed by the development, must be submitted with the *Construction Certificate* application.

Note: This condition is imposed to ensure that the existing structure structural is able to support the additional loads proposed.

C.5 Professional Engineering Details

The *Construction Certificate* plans and specifications, required by clause 139 of the Regulation, must include detailed *professional engineering* plans and specifications for all structural, electrical, hydraulic, hydro-geological, geotechnical, mechanical and civil work complying with this consent, approved plans, the statement of environmental effects and supporting documentation.

Detailed professional engineering plans and specifications must be submitted to the *Certifying Authority* with the application for any *Construction Certificate*.

C.6 Works Zone

A Work Zone (Construction Zone) is required for this development. Prior to issue of the Construction Certificate an application for the required Works Zone must be submitted to Woollahra Council, for consideration by the Woollahra Local Traffic Committee.

Prior to commencement of any demolition, land clearing, piling, piercing, excavation, construction or like work or the issue of a Notice of Commencement of building works, any Works Zone approval by the Woollahra Local Traffic Committee shall be implemented strictly in accordance with the Committee's terms and conditions.

Note:

- The Woollahra Local Traffic Committee meets monthly.
- A minimum of eight weeks is required for assessment and determination of a Works Zone application.
- Failure to comply with this condition may result in fines and proceedings pursuant to Part 6 of the *Environmental Planning & Assessment Act 1979*.

C.7 Amended Landscape Plan

An Amended Landscape Plan, prepared by a qualified Landscape Architect or Landscape Designer, to a scale of 1:100 or 1:200, conforming to the conditions of this Development Consent is to be submitted to Council for approval prior to issue of the Construction Certificate. The plan must include a detailed planting schedule, which must include species listed by botanical and common names, quantities of each species, pot sized, and the estimated size of the plant at maturity.

C.8 Trees which may be removed (C8)

This consent includes approval under Council's Tree Preservation Order to remove the following trees:

Council Reference No:	Species	Location	Dimension (Metres)
1	<i>Liquidamber styraciflua</i> (Liquidambar)	Northern boundary adjacent to driveway entry	8 (h) x 5 (w)

The Construction Certificate plans must include reference to the removal of the above mentioned trees and identify the trees by Council's reference number (Council Ref No:) and colour or shade them in the colour red.

C.9 Vehicular access and garaging

Driveways and access ramps must be designed not to scrape the underside of cars.

In all other respects, proposed garage/car park/basement car park, driveways and access ramps must be designed to comply with Australian Standard AS 2890.1 – "Off-Street car parking."

The plans are to be amended to comply with the following:

- To prevent ingress of water off the ROW a new 11m wide layback in accordance with Council's Standard Drawing RF2 is to be constructed. Levels in the footpath area must match existing.
- A new traffic mirror is to be installed on the northern side of the ROW at the first corner approx 15.5m from the street boundary

The revised details submitted to the certifier for approval prior to issue of Construction Certificate

C.10 Hydrogeological and Geotechnical Monitoring Program

Excavation works associated with the proposed development must be overseen and monitored by a qualified and practising geotechnical engineer. A Hydrogeological and Geotechnical Monitoring Program must be produced to ensure that all geotechnical matters are regularly assessed during the construction to prevent adverse effects resulting from the excavation.

The Hydrogeological and Geotechnical Monitoring Program for the construction works must be in accordance with the recommendations of the Geotechnical and Hydrogeological Report prepared by Martens Consulting Engineers Ref P0501324JR01_v1 dated March 2006

Prior to the issue of a Construction Certificate, the applicant must submit to the Accredited Certifier details of the proposed Hydrogeological and Geotechnical Monitoring Program. A suitably qualified and practising geotechnical engineer must prepare the Program which must consist of the following;

- Recommendations as contained within the Geotechnical and Hydrogeological Report prepared by Martens Consulting Engineers Ref P0501324JR01_v1 dated March 2006
- Recommended hold points to allow for inspection by a geotechnical engineer during the following construction procedures;
 - ▶ Excavation of the site (face of excavation, base, etc)
 - ▶ Installation and construction of temporary and permanent shoring/ retaining walls.
 - ▶ Foundation bearing conditions and footing construction.
 - ▶ Installation of sub-soil drainage.
- Location, type and regularity of further geotechnical/hydrogeological investigations and testing.

C.11 Vibration Monitoring Program

Vibration resulting from construction activities can adversely affect surrounding property and infrastructure. To ensure that vibration created by the method of construction does not adversely impact on the existing building, surrounding property and infrastructure, a Vibration Monitoring Program must be implemented.

Prior to the issue of the Construction Certificate, the applicant must submit to the Accredited Certifier details of the proposed Vibration Monitoring Program. A qualified and practising geotechnical and/or hydrogeological engineer must prepare the Vibration Monitoring Program and undertake all associated investigations. Details to be included in Vibration Monitoring Program to include:

- a) pre-set acceptable limits for the variation of:
 - settlement
 - deflection or movement of retaining mechanisms such as shoring and bracing and
 - vibration in accordance with AS 2187.2 1993 Appendix J, including acceptable velocity of vibration.
- b) the location and type of monitoring systems to be used
- c) recommended hold points to allow for inspection and certification by a geotechnical engineer and
- d) a contingency plan should the pre-set acceptable limits be exceeded.

D. Conditions which must be satisfied prior to the commencement of any development work

D.1 Compliance with Building Code of Australia and insurance requirements under the Home Building Act 1989

For the purposes of section 80A (11) of the Act, the following conditions are prescribed in relation to a development consent for development that involves any building work:

- a) that the work must be carried out in accordance with the requirements of the Building Code of Australia,
- b) in the case of residential building work for which *the Home Building Act 1989* requires there to be a contract of insurance in force in accordance with Part 6 of that Act, that such a contract of insurance is in force before any building work authorised to be carried out by the consent commences.

This condition does not apply:

- a) to the extent to which an exemption is in force under clause 187 or 188, subject to the terms of any condition or requirement referred to in clause 187 (6) or 188 (4),
or
- b) to the erection of a temporary building.

In this condition, a reference to the *BCA* is a reference to that code as in force on the date the application for the relevant construction certificate is made.

Note: This condition must be satisfied prior to commencement of any work in relation to the contract of insurance under the *Home Building Act 1989*. This condition also has effect during the carrying out of all building work with respect to compliance with the Building Code of Australia.

D.2 Building - Construction Certificate, Appointment of Principal Certifying Authority, Appointment of Principal Contractor and Notice of Commencement (s81A(2) of the Act)

The erection of the building in accordance with this development consent must not be commenced until:

- (a) a construction certificate for the building work has been issued by the consent authority, the council (if the council is not the consent authority) or an accredited Certifier, and

- (b) the person having the benefit of the development consent has:
appointed a principal certifying authority for the building work, and
notified the principal certifying authority that the person will carry out the building work as an owner-builder, if that is the case, and
- (b1) the principal certifying authority has, no later than 2 days before the building work commences:
notified the consent authority and the council (if the council is not the consent authority) of his or her appointment, and
notified the person having the benefit of the development consent of any critical stage inspections and other inspections that are to be carried out in respect of the building work, and
- (b2) the person having the benefit of the development consent, if not carrying out the work as an owner-builder, has:
appointed a principal contractor for the building work who must be the holder of a contractor licence if any residential building work is involved, and
notified the principal certifying authority of any such appointment, and
unless that person is the principal contractor, notified the principal contractor of any critical stage inspections and other inspections that are to be carried out in respect of the building work, and
given at least 2 days' notice to the council of the person's intention to commence the erection of the building.
- Note:** *building* has the same meaning as in section 4 of the *Act* and includes part of a building and any structure or part of a structure.
- Note:** *new building* has the same meaning as in section 109H of the *Act* and includes an altered portion of, or an extension to, an existing building.
- Note:** The commencement of demolition works associated with an altered portion of, or an extension to, an existing building is considered to be the commencement of building work requiring compliance with section 82A(2) of the *Act* (including the need for a *Construction Certificate*) prior to any demolition work. See: *Over our Dead Body Society Inc v Byron Bay Community Association Inc* [2001] NSWLEC 125.
- Note:** *Construction Certificate* Application, *PCA Service Agreement* and *Notice of Commencement* forms can be downloaded from Council's website www.woollahra.nsw.gov.au.
- Note:** It is an offence for any person to carry out the erection of a *building* in breach of this condition and in breach of section 81A(2) of the *Act*.

D.3 Construction Certificate required prior to any demolition

Where demolition is associated with an altered portion of, or an extension to an existing building the demolition of any part of a building is "commencement of erection of building" pursuant to section 81A(2) of the Act. In such circumstance all conditions in Part C and Part D of this consent must be satisfied prior to any demolition work. This includes, but is not limited to, the issue of a Construction Certificate, appointment of a PCA and Notice of Commencement under the Act.

Note: See *Over our Dead Body Society Inc v Byron Bay Community Association Inc* [2001] NSWLEC 125.

D.4 Protection of services

Prior to any excavation works, the location and depth of all services (telephone, cable TV, electricity, gas, water, sewer, drainage, etc.) must be ascertained. The developer must meet all costs of any adjustment, relocation or reinstatement of any services.

D.5 Road Opening Permit

Prior to the commencement of any excavation in Council controlled roadways or footpath areas, the developer must obtain a road opening permit from Council's Customer Services Counter. Restoration of roads, footpaths, retaining walls, kerbs and gutters must be carried out in accordance with the relevant clauses of the current edition of AUS-SPEC.

D.6 Dilapidation Reports for existing buildings/structures

Dilapidation surveys must be conducted and dilapidation reports prepared by a *professional engineer* (structural) of all buildings/structures on land whose title boundary abuts the site and of such further buildings/structures located within the likely "zone of influence" of any excavation, dewatering and/or construction induced vibration.

These properties must include (but is not limited to):

The elevated structure in the adjoining Right of Way to the north for the full length
The dilapidation reports must be completed and submitted to Council with the Notice of Commencement prior to the commencement of any development work.

Where excavation of the site will extend below the level of any immediately adjoining building/structure the principal contractor or owner builder must give the adjoining building owner(s) a copy of the dilapidation report for their building(s) and a copy of the notice of commencement required by s81A(2) of the Act not less than two (2) days prior to the commencement of any work.

A second dilapidation report, recording structural conditions of all structures originally assessed prior to the commencement of works, must be carried out at the completion of the works and be submitted to Council.

D.7 Notification of Home Building Act 1989 requirements

- (1) For the purposes of section 80A (11) of the Act, the requirements of this condition are prescribed as conditions of a development consent for development that involves any residential building work within the meaning of the Home Building Act 1989.

- (2) Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the principal certifying authority for the development to which the work relates (not being the council) has given the council written notice of the following information:
 - (a) in the case of work for which a *principal contractor* is required to be appointed:
 - (i) the name and licence number of the principal contractor, and
 - (ii) the name of the insurer by which the work is insured under Part 6 of that Act,
 - (b) in the case of work to be done by an owner-builder:
 - (i) the name of the owner-builder, and
 - (ii) if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.
- (3) If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under subclause (2) becomes out of date, further work must not be carried out unless the principal certifying authority for the development to which the work relates (not being the council) has given the council written notice of the updated information.
- (4) This clause does not apply in relation to Crown building work that is certified, in accordance with section 116G of the Act, to comply with the technical provisions of the State's building laws.

D.8 Site Signs

The *Principal Contractor* or *owner builder* must ensure that the sign required by clauses 98A and 227A of the *Regulation* is erected and maintained at all times.

“Erection of signs

- (1) For the purposes of section 80A (11) of the *Act*, the requirements of subclauses (2) and (3) are prescribed as conditions of a development consent for development that involves any building work, subdivision work or demolition work.
- (2) A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:
 - (a) showing the name, address and telephone number of the principal certifying authority for the work, and
 - (b) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
 - (c) stating that unauthorised entry to the work site is prohibited.
- (3) Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.
- (4) This clause does not apply in relation to building work, subdivision work or demolition work that is carried out inside an existing building that does not affect the external walls of the building.
- (5) This clause does not apply in relation to Crown building work that is certified, in accordance with section 116G of the Act, to comply with the technical provisions of the State's building laws.”

Note: *PCA* and *principal contractors* must also ensure that signs required by this clause are erected and maintained (see clause 227A which imposes a penalty exceeding \$1,000).

Note: If *Council* is appointed as the *PCA* it will provide the sign to the *principal contractor* or *owner builder* who must ensure that the sign is erected and maintained as required by Clause 98A of the *Regulation*.

D.9 Toilet Facilities

Toilet facilities are to be provided, at or in the vicinity of the work site on which work involved in the erection or demolition of a building is being carried out, at the rate of one toilet for every 20 persons or part of 20 persons employed at the site.

Each toilet provided:

- a) must be a standard flushing toilet, and
- b) must be connected to a public sewer, or
- c) if connection to a public sewer is not practicable, to an accredited sewage management facility approved by the council, or
- d) if connection to a public sewer or an accredited sewage management facility is not practicable, to some other sewage management facility approved by the council.

The provision of toilet facilities in accordance with this condition must be completed before any other work is commenced.

In this condition:

accredited sewage management facility means a sewage management facility to which Division 4A of Part 3 of the *Local Government (Approvals) Regulation 1993* applies, being a sewage management facility that is installed or constructed to a design or plan the subject of a certificate of accreditation referred to in clause 95B of the *Local Government (Approvals) Regulation 1993*.

approved by the council means the subject of an approval in force under Division 1 of Part 3 of the *Local Government (Approvals) Regulation 1993*.

public sewer has the same meaning as it has in the *Local Government (Approvals) Regulation 1993*.

sewage management facility has the same meaning as it has in the *Local Government (Approvals) Regulation 1993*.

Note: This condition does not set aside the requirement to comply with Workcover NSW requirements.

D.10 Erosion and Sediment Controls – Installation

The *principal contractor* or *owner builder* must install and maintain water pollution, erosion and sedimentation controls in accordance with:

- a) The *Soil and Water Management Plan* if required under this consent;
- b) “*Do it Right On Site, Soil and Water Management for the Construction Industry*” published by the Southern Sydney Regional Organisation of Councils, 2001; and
- c) “*Managing Urban Stormwater - Soils and Construction*” published by the NSW Department of Housing 4th Edition” (“The Blue Book”).

Where there is any conflict The Blue Book takes precedence.

- Note:** The International Erosion Control Association – Australasia (<http://www.austieca.com.au/>) lists consultant experts who can assist in ensuring compliance with this condition. Where Soil and Water Management Plan is required for larger projects it is recommended that this be produced by a member of the International Erosion Control Association – Australasia.
- Note:** The “Do it Right On Site, Soil and Water Management for the Construction Industry” publications can be down loaded free of charge from www.woollahra.nsw.gov.au.
- Note:** A failure to comply with this condition may result in penalty infringement notices, prosecution, notices and orders under the Act and/or the *Protection of the Environment Operations Act 1997* **without any further warning**. It is a criminal offence to cause, permit or allow pollution.
- Note:** Section 257 of the *Protection of the Environment Operations Act 1997* provides inter alia that “the occupier of premises at or from which any pollution occurs is taken to have caused the pollution”
- Warning,** Irrespective of this condition any person occupying the site may be subject to proceedings under the *Protection of the Environment Operations Act 1997* where pollution is caused, permitted or allowed as the result of their occupation of the land being developed.

D.11 Notification of Home Building Act 1989 requirements

- (1) For the purposes of section 80A (11) of the Act, the requirements of this condition are prescribed as conditions of a development consent for development that involves any residential building work within the meaning of the Home Building Act 1989.
- (2) Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the principal certifying authority for the development to which the work relates (not being the council) has given the council written notice of the following information:
 - (a) in the case of work for which a *principal contractor* is required to be appointed:
 - (i) the name and licence number of the principal contractor, and
 - (ii) the name of the insurer by which the work is insured under Part 6 of that Act,
 - (b) in the case of work to be done by an owner-builder:
 - (i) the name of the owner-builder, and
 - (ii) if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.
- (3) If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under subclause (2) becomes out of date, further work must not be carried out unless the principal certifying authority for the development to which the work relates (not being the council) has given the council written notice of the updated information.
- (4) This clause does not apply in relation to Crown building work that is certified, in accordance with section 116G of the Act, to comply with the technical provisions of the State’s building laws.

E. Conditions which must be satisfied during any development work

E.1 Compliance with Building Code of Australia and insurance requirements under the Home Building Act 1989

For the purposes of section 80A (11) of the Act, the following condition is prescribed in relation to a development consent for development that involves any building work:

- a) that the work must be carried out in accordance with the requirements of the Building Code of Australia,
- b) in the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, that such a contract of insurance is in force before any building work authorised to be carried out by the consent commences.

This condition does not apply:

- a) to the extent to which an exemption is in force under clause 187 or 188, subject to the terms of any condition or requirement referred to in clause 187 (6) or 188 (4) of the Regulation, or
- b) to the erection of a temporary building.

In this clause, a reference to the BCA is a reference to that Code as in force on the date the application for the relevant construction certificate is made.

E.2 Compliance with Australian Standard for Demolition

Demolition of buildings and structures must comply with Australian Standard AS 2601—1991: The Demolition of Structures, published by Standards Australia, and as in force at 1 July 1993.

E.3 Requirement to notify about new evidence

Any new information which comes to light during remediation, demolition or construction works which has the potential to alter previous conclusions about site contamination, heritage significance, threatened species or other relevant matters must be immediately notified to Council and the Principal Certifying Authority.

E.4 Critical Stage Inspections

Critical stage inspections must be called for by the *principal contractor* or *owner builder* as required by the PCA, any PCA service agreement, the *Act* and the *Regulation*.

Work must not proceed beyond each critical stage until the PCA is satisfied that work is proceeding in accordance with this consent, the Construction Certificate(s) and the *Act*. *critical stage inspections* means the inspections prescribed by the *Regulations* for the purposes of section 109E(3)(d) of the *Act* or as required by the *PCA* and any *PCA Service Agreement*.

Note: The PCA may require inspections beyond mandatory critical stage inspections in order that the PCA be satisfied that work is proceeding in accordance with this consent.

Note: The PCA may, in addition to inspections, require the submission of *Compliance Certificates*, survey reports or evidence of suitability in accordance with Part A2.2 of the BCA in relation to any matter relevant to the development.

E.5 Hours of Work –Amenity of the neighbourhood

- a) No *work* must take place on any Sunday or public holiday,
- b) No *work* must take place before 7am or after 5pm any weekday,
- c) No *work* must take place before 7am or after 1pm any Saturday, and
- d) No piling, piling, cutting, boring, drilling, rock breaking, rock sawing, jack hammering or bulk excavation of land or loading of material to or from trucks must take place before 9am or after 4pm any weekday, or before 9am or after 1pm any Saturday.
- e) No rock excavation being cutting, boring, drilling, breaking, sawing, jack hammering or bulk excavation of rock, must occur without a 15 minute break every hour.

This condition has been imposed to mitigate the impact of work upon the amenity of the neighbourhood. Impact of work includes, but is not limited to, noise, vibration, dust, odour, traffic and parking impacts.

Note: The use of noise and vibration generating plant and equipment and vehicular traffic, including trucks in particular, significantly degrade the amenity of neighbourhoods and more onerous restrictions apply to these activities. This more invasive work generally occurs during the foundation and bulk excavation stages of development. If you are in doubt as to whether or not a particular activity is considered to be subject to the more onerous requirement (9am to 4pm weekdays and 9am to 1pm Saturdays) please consult with Council.

Note: Each and every breach of this condition by any person may be subject to separate penalty infringement notice or prosecution.

Note: The delivery and removal of plant, equipment and machinery associated with wide loads subject to RTA and Police restrictions on their movement outside the approved hours of work will be considered on a case by case basis.

Note: Compliance with these hours of work does not affect the rights of any person to seek a remedy to offensive noise as defined by the *Protection of the Environment Operations Act 1997*, the *Protection of the Environment Operations (Noise Control) Regulation 2000*.

Note: EPA Guidelines can be downloaded from <http://www.epa.nsw.gov.au/noise/nglg.htm> .

Note: See http://www.epa.nsw.gov.au/resources/ci_build_sheet7.pdf

E.6 Connection to existing drainage system

Stormwater run-off from the proposed works must drain to the existing stormwater drainage system.

The existing stormwater drainage pipes on the property affected by the development must be checked and certified by a practising hydraulic engineer to ensure that existing stormwater pipes are in good condition and are operating satisfactorily. Certification and a plan showing pipe locations and diameters must be submitted to the Accredited Certifier prior to the issue of the final Occupation Certificate.

If the existing stormwater pipes are not in good condition and/or not operating satisfactorily, the existing drainage system must be upgraded. Certification and a plan showing pipe locations and diameters of the upgraded system must be submitted to the Accredited Certifier prior to the issue of the final Occupation Certificate.

Stormwater disposal is to comply with the requirements and conditions as set out in Council's Draft Stormwater Drainage Management DCP (Draft Version 1, Public Exhibition Copy dated 23/08/2004). This is available from Council's website <http://www.woollahra.nsw.gov.au>.

Note: connection of stormwater run-off to the Sydney Water sewer system is not permitted.

E.7 Stockpiles

Stockpiles of topsoil, sand, aggregate, soil or other material must not be located on any drainage line or easement, natural watercourse, footpath or roadway, or within the dripline of any Street Tree. Stockpiles within the construction site must be protected with adequate sediment controls, in accordance with Council's Code for Sediment Control.

E.8 Erosion and sediment control

Erosion and sediment controls, designed in accordance with the SSROC Soil and Water Management Brochure and the NSW Environmental Protection Authority's *Managing Urban Stormwater: Construction Activities*, must be implemented during demolition, excavation and construction of the development. All controls must be maintained at all times.

E.9 Location of building operations

Building operations such as brick cutting, washing tools or brushes and mixing mortar must not take place on public roadways or footways or in any other location which could lead to the discharge of materials into the stormwater drainage system.

Footpaths, gutters and roadways must be swept regularly to keep them free from sediment.

E.10 Compliance with the construction management plan

All excavation, demolition and construction work and traffic movements must be carried out in accordance with the approved construction management plan. All controls in the Plan must be maintained at all times. A copy of the Plan must be kept on-site at all times and made available to the PCA or Council on request.

E.11 Footpath levels

The existing footpath level and grade at the street alignment of the property must be maintained.

E.12 Public footpaths

A safe pedestrian circulation route a minimum of 1.5m wide and with a pavement free of trip hazards must be maintained at all times on or adjacent to the public footpaths fronting the construction site. Where the footpath is damaged, repair works must be carried when directed by Council officers and in accordance with the relevant clauses of the current edition of AUS-SPEC.

Where circulation is diverted on to the roadway clear directional signage and protective barricades must be installed in accordance with Aust AS1742-3 1996 “*Traffic Control Devices for Work on Roads*”.

If pedestrian circulation is not satisfactorily maintained, and action is not taken promptly to rectify the defects, Council may carry out remedial works and deduct the cost from the Damage Security Deposit.

E.13 Repair of Damaged Infrastructure

If Council’s infrastructure is damaged during the course of works, Council’s Development Engineer must be notified and necessary repairs must be undertaken within the time stipulated by Council, to Council’s specifications, and at no cost to Council. Works generally must be in accordance with the relevant clauses of the current edition of AUS-SPEC.

If work is not undertaken to the satisfaction of the Development Engineer with regard to time or quality, Council may carry out remedial works and deduct the cost from the Damage Security Deposit.

E.14 Compliance with the recommendations of the geotechnical and hydrogeological reports

The development works are to be undertaken in accordance with the recommendations of the Geotechnical and Hydrogeological report prepared by Martens Consulting Engineers Ref P0501324JR01_v1 dated March 2006

E.15 Erosion and Sediment Controls – Maintenance

The *principal contractor* or *owner builder* must maintain water pollution, erosion and sedimentation controls in accordance with:

- a) The Soil and Water Management Plan required under this consent;
- b) “*Do it Right On Site, Soil and Water Management for the Construction Industry*” published by the Southern Sydney Regional Organisation of Councils, 2001; and
- c) “*Managing Urban Stormwater - Soils and Construction*” published by the NSW Department of Housing 4th Edition (“*The Blue Book*”).

Where there is any conflict The Blue Book takes precedence.



Note 1: A failure to comply with this condition may result in penalty infringement notices, prosecution, notices and orders under the Act and/or the Protection of the Environment Operations Act 1997 without any further warning. It is a criminal offence to cause, permit or allow pollution.

Note 2: Section 257 of the Protection of the Environment Operations Act 1997 provides that “the occupier of premises at or from which any pollution occurs is taken to have caused the pollution”.

Warning, Irrespective of this condition any person occupying the site may be subject to proceedings under the Protection of the Environment Operations Act 1997 where pollution is caused, permitted or allowed as the result of the occupation of the land being developed whether or not they actually cause the pollution.

E.16 Dust Mitigation

Dust mitigation must be implemented in accordance with “*Dust Control - Do it right on site*” published by the Southern Sydney Regional Organisation of Councils.

This generally requires:

- a) Dust screens to all hoardings and site fences.
- b) All stockpiles or loose materials to be covered when not being used.
- c) All equipment, where capable, being fitted with dust catchers.
- d) All loose materials being placed bags before placing into waste or skip bins.
- e) All waste and skip bins being kept covered when not being filled or emptied.
- f) The surface of excavation work being kept wet to minimise dust.
- g) Landscaping incorporating trees, dense shrubs and grass being implemented as soon as practically possible to minimise dust.

Note 1: “*Dust Control - Do it right on site*” can be down loaded free of charge from Council’s web site www.woollahra.nsw.gov.au or obtained from Council’s office.

Note 2: Special precautions must be taken when removing asbestos or lead materials from development sites. Additional information can be obtained from www.workcover.nsw.gov.au and www.epa.nsw.gov.au . Other specific condition and advice may apply.

Note 3: Demolition and construction activities may affect local air quality and contribute to urban air pollution. The causes are dust, smoke and fumes coming from equipment or activities, and airborne chemicals when spraying for pest management. Precautions must be taken to prevent air pollution.

E.17 Existing drainage easement, drainage reserve or stormwater drainage system benefiting Council

Council drainage easement(s) drainage reserve(s) or stormwater system passes through the site. No building or other structure must be placed over the drainage easement or stormwater system or within the zone of influence taken from the invert of any pipe.

The *principal contractor* or *owner builder* must locate all *Stormwater Drainage Systems* without causing any damage to the public system and ensure its protection. The *owner*, *principal contractor* or *owner builder* must not obstruct or otherwise remove, disconnect or render inoperable the *Stormwater Drainage System*.

Works such as fences must not obstruct the natural floodway or alter the natural floodway in such a way as to direct or concentrate stormwater on to neighbouring properties.

Where the relocation or reconstruction of Council’s drainage system is approved then all work carried out on assets which are under Council ownership or will revert to the ownership, care, control or management of Council, in connection with the *development* to which this consent relates, must comply with Council’s *Specification for Roadworks, Drainage and Miscellaneous Works* dated January 2003.

The *owner, principal contractor* or *owner builder* must meet all costs associated with such works.

E.18 Protection of services

Prior to any excavation works, the location and depth of all services (telephone, cable TV, electricity, gas, water, sewer, drainage, etc.) must be ascertained. The developer must meet all costs of any adjustment, relocation or reinstatement of any services.

E.19 Compliance with the Hydrogeological and Geotechnical Monitoring Program

Excavation and construction works must be undertaken in accordance with the “Geotechnical and Hydrogeological Monitoring Program” submitted as required by condition of consent.

A qualified and registered geotechnical engineer shall provide certification to the Accredited Certifier that all earth works have been carried out;

- In accordance with the Hydrogeological and Geotechnical Monitoring Program.
- In accordance with the relevant Australian Standards and Codes of Practise.
- In a manner that does not compromise the structural integrity of all adjacent structures, property and infrastructure.

The certification and a complete record of inspections, testing and monitoring (with certifications) must be submitted in report form to the Accredited Certifier for approval, prior to the issue of a Final Building Certificate.

F. Conditions which must be satisfied prior to any occupation or use of the building (Part 4A of the Act and Part 8 Division 3 of the Regulation)

F.1 Occupation Certificate (section 109M of the Act)

A person must not commence occupation or use of the whole or any part of a new building (within the meaning of section 109H (4) of the *Act*) unless an occupation certificate has been issued in relation to the building or part.

Note: new building includes an altered portion of, or an extension to, an existing building.

G. Conditions which must be satisfied prior to the issue of any Subdivision Certificate

No relevant conditions.

H. Conditions which must be satisfied prior to the issue of a Final Occupation Certificate (s109C(1)(c))

H.1 Compliance with the Hydrogeological and Geotechnical Monitoring Program

Excavation and construction works must be undertaken in accordance with the “Geotechnical and Hydrogeological Monitoring Program” submitted as required by condition of consent.

A qualified and registered geotechnical engineer shall provide certification to the Accredited Certifier that all earth works have been carried out;

- In accordance with the Hydrogeological and Geotechnical Monitoring Program.
- In accordance with the relevant Australian Standards and Codes of Practise.
- In a manner that does not compromise the structural integrity of all adjacent structures, property and infrastructure.

The certification and a complete record of inspections, testing and monitoring (with certifications) must be submitted in report form to the Accredited Certifier for approval, prior to the issue of a Final Occupation Certificate.

H.2 Certification of Vibration Monitoring

A record of inspections and monitoring of vibration in accordance with the Vibration Monitoring Program must be submitted in a report form to the Accredited Certifier prior to release of the Certificate of Occupancy or final building inspection as appropriate. A qualified and practising geotechnical and/or hydrogeological engineer must prepare certification.

H.3 Replacement trees which must be planted

The following compensatory replacement plantings must be planted to ensure the preservation of the landscape character of the area.

Species/Type	Planting Location	Container Size or Size of Tree (@ time of planting)	Minimum Dimensions at Maturity
<i>Elaeocarpus reticulatus</i> (Blueberry Ash)	Same position as removed <i>Liquidamber styraciflua</i> (Liquidambar)	200 litre	10 Height 6 spread

I. Conditions which must be satisfied during the ongoing use of the development

No relevant conditions.

J. Miscellaneous Conditions

No relevant conditions.

D6 DA702/2006 – 8 Wyuna Road, Point Piper – New swimming pool & landscaping to front of property – 6/10/2006

Note: Ms C Pidcock the Architect, addressed the Panel.

Note: The Panel had regard to the controls C.5.3.16 to C.5.3.22 of the Residential DCP 2003 which relate to swimming pools and spa pools.

(Bluett/Hatton)

Resolved: Pursuant to Section 80(1) of the Environmental Planning and Assessment Act, 1979

THAT the Council, as the consent authority, grant development consent to Development Application No. 702/2006 for new swimming pool and landscaping to front of property on land at 8 Wyuna Road Point Piper, subject to the following conditions:

A. General Conditions

A.1 Conditions

Consent is granted subject to the following conditions imposed pursuant to section 80 of the Environmental Planning & Assessment Act 1979 (“the *Act*”) and the provisions of the Environmental Planning and Assessment Regulation 2000 (“the *Regulation*”) such conditions being reasonable and relevant to the development as assessed pursuant to section 79C of the Act.

A.2 Definitions

Unless specified otherwise words have the same meaning as defined by the *Act*, the *Regulation* and the *Interpretation Act 1987* as in force at the date of consent.

Applicant means the applicant for this Consent.

Approved Plans mean the plans endorsed by Council referenced by this consent as amended by conditions of this consent.

AS or *AS/NZS* means Australian Standard® or Australian/New Zealand Standard®, respectively, published by Standards Australia International Limited.

BCA means the Building Code of Australia as published by the Australian Building Codes Board as in force at the date of issue of any *Construction Certificate*.

Council means Woollahra Municipal Council

Court means the Land and Environment Court

Local native plants means species of native plant endemic to Sydney’s eastern suburbs (see the brochure titled “Local Native Plants for Sydney’s Eastern Suburbs published by the Southern Sydney Regional Organisation of Councils).

Stormwater Drainage System means all works, facilities and documentation relating to:

- a) The collection of stormwater,
- b) The retention of stormwater,
- c) The reuse of stormwater,
- d) The detention of stormwater,
- e) The controlled release of stormwater; and
- f) Connections to easements and public stormwater systems.

Owner means the owner of the *site* and successors in title to the *site*.

Owner Builder has the same meaning as in the *Home Building Act 1989*.

PCA means the *Principal Certifying Authority* under the *Act*.

Principal Contractor has the same meaning as in the *Act* or where a *principal contractor* has not been appointed by the *owner* of the land being developed *Principal Contractor* means the *owner* of the land being developed.

Professional Engineer has the same meaning as in the *BCA*.

Public Place has the same meaning as in the *Local Government Act 1993*.

Road has the same mean as in the *Roads Act 1993*.

SEE means the final version of the Statement of Environmental Effects lodged by the *Applicant*.

Site means the land being developed subject to this consent.

WLEP 1995 means *Woollahra Local Environmental Plan 1995*

Work for the purposes of this consent means:

- a) the use of land in connection with development,
- b) the subdivision of land,
- c) the erection of a building,
- d) the carrying out of any work,
- e) the use of any site crane, machine, article, material, or thing,
- f) the storage of waste, materials, site crane, machine, article, material, or thing,
- g) the demolition of a building,
- h) the piling, piering, cutting, boring, drilling, rock breaking, rock sawing or excavation of land,
- i) the delivery to or removal from the *site* of any machine, article, material, or thing, or
- j) the occupation of the *site* by any person unless authorised by an *occupation certificate*.

Note: Interpretation of Conditions - Where there is any need to obtain an interpretation of the intent of any condition this must be done in writing to Council and confirmed in writing by Council.

A.3 Approved Plans and supporting documents

Those with the benefit of this consent must carry out all work and maintain the use and works in accordance with the plans and supporting documents listed below as submitted by the Applicant and to which is affixed a Council stamp “Approved DA Plans” **unless modified by any following condition**. Where the plans relate to alterations or additions only those works shown in colour or highlighted are approved.

Reference	Description	Author/Drawn	Date(s)
DA200A – DA205A (inclusive)	Architectural Plans	Caroline Pidcock Archtiects	4 October 2006

Note: Warning to Accredited Certifiers – You should always insist on sighting the original Council stamped approved plans. You should not rely solely upon the plan reference numbers in this condition. Should the applicant not be able to provide you with the original copy Council will provide you with access to its files so you may review our original copy of the approved plan.

Note: These plans and supporting documentation may be subject to conditions imposed under section 80A(1)(g) of the *Act* modifying or amending the development (refer to conditions which must be satisfied prior to the issue of any *Construction Certificate*.)

A.4 Prescribed Conditions

Prescribed conditions in force under the *Act* and *Regulation* must be complied with.

Note: It is the responsibility of those acting with the benefit of this consent to comply with all prescribed conditions under the *Act* and the *Regulation*. Free access can be obtained to all NSW legislation at www.legislation.nsw.gov.au

B. Conditions which must be satisfied prior to the demolition of any building or construction

B.1 Construction Certificate required prior to any demolition

Where demolition is associated with an altered portion of, or an extension to an existing building the demolition of any part of a building is "commencement of erection of building" pursuant to section 81A(2) of the Act. In such circumstance all conditions in Part C and Part D of this consent must be satisfied prior to any demolition work. This includes, but is not limited to, the issue of a Construction Certificate, appointment of a PCA and Notice of Commencement under the Act.

Note: See *Over our Dead Body Society Inc v Byron Bay Community Association Inc* [2001] NSWLEC 125.

C. Conditions which must be satisfied prior to the issue of any construction certificate

C.1 Payment of Security, Levies and Fees (S80A(6) & S94 of the Act, Section 608 of the Local Government Act 1993)

The person(s) with the benefit of this consent must pay the following long service levy, security, development levy, and fees prior to the issue of any *construction certificate*, *subdivision certificate* or *occupation certificate*, as will apply.

The *certifying authority* must not issue any *Part 4A Certificate* until provided with the original receipt(s) for the payment of all of the following levy, security, contributions, and fees. Specifically

- a) prior to the issue of a *construction certificate*, where a construction certificate is required; or
- b) prior to the issue of a *subdivision certificate*, where only a subdivision certificate is required; or
- c) prior to the issue of an *occupation certificate* in any other instance.

Description	Amount	Indexed	Council Fee Code
LONG SERVICE LEVY under Building and Construction Industry Long Service Payments Act 1986			
Long Service Levy Use Calculator: http://www.lspc.nsw.gov.au/levy_information/?levy_information/levy_calculator.stm	Contact LSL Corporation or use their online calculator	No	
SECURITY under section 80A(6) of the Environmental Planning and Assessment Act 1979			
Property Damage Security Deposit - Making good any damage caused to any property of the <i>Council</i> as a consequence of the doing of anything to which the consent relates.	\$2000.00	No	T600

DEVELOPMENT LEVY under Woollahra Section 94A Development Contributions Plan 2005 This plan may be inspected at Woollahra Council or downloaded from our website www.woollahra.nsw.gov.au .			
Development Levy	\$755.00 + Index Amount	Yes, quarterly	T94
INSPECTION FEES under section 608 of the Local Government Act 1993			
Security Administration Fee	\$163.00	No	T16
TOTAL SECURITY, CONTRIBUTIONS, LEVIES AND FEES	\$2918.00 Plus any relevant indexed amounts and long service levy		

Building & Construction Industry Long Service Payment

The Long Service Levy under Section 34 of the *Building & Construction Industry Long Service Payment Act, 1986*, must be paid and proof of payment provided to the *Certifying Authority* prior to the issue of any *Construction Certificate*.

Note: The Levy can be paid directly to the Long Services Payments Corporation or to Council. Further information can be obtained from the Long Service Payments Corporation's website <http://www.lspc.nsw.gov.au/> or by telephoning the Long Service Payments Corporation on 13 14 41.

How must the payments be made?

Payments must be made by:

1. Cash deposit with Council,
2. Credit card payment with Council, or
3. Bank cheque made payable to Woollahra Municipal Council.

The payment of a security may be made by a bank guarantee where:

- a) the guarantee is by an Australian bank for the amount of the total outstanding contribution;
- b) the bank unconditionally agrees to pay the guaranteed sum to the Council on written request by Council on completion of the development or no earlier than 12 months from the provision of the guarantee whichever occurs first;
- c) the bank agrees to pay the guaranteed sum without reference to the applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent; and
- d) the bank's obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required.

How will the section 94A levy be indexed?

To ensure that the value the development levy is not eroded over time by increases in costs, the proposed cost of carrying out development (from which the development levy is calculated) will be indexed either annually or quarterly (see table above). Clause 3.13 of the Woollahra Section 94A Development Contributions Plan 2005 sets out the formula and index to be used in adjusting the s.94A levy.

Do you need HELP indexing the levy?

Please contact our customer service officers. Failure to correctly calculate the adjusted the development levy will delay the issue of any Part 4A Certificate and could void any Part 4A Certificate (construction certificate, subdivision certificate, or occupation certificate).

Deferred periodic payment of section 94A levy under the Woollahra Section 94A Development Contributions Plan 2005

Where the applicant makes a written request supported by reasons for payment of the section 94A levy other than as required by clause 3.9, the Council may accept deferred or periodic payment. The decision to accept a deferred or periodic payment is at the sole discretion of the Council, which will consider:

- a) the reasons given;
- b) whether any prejudice will be caused to the community deriving benefit from the public facilities;
- c) whether any prejudice will be caused to the efficacy and operation of this plan; and
- d) whether the provision of public facilities in accordance with the adopted works schedule will be adversely affected.

Council may, as a condition of accepting deferred or periodic payment, require the provision of a bank guarantee where:

- a) the guarantee is by an Australian bank for the amount of the total outstanding contribution;
- b) the bank unconditionally agrees to pay the guaranteed sum to the Council on written request by Council on completion of the development or no earlier than 12 months from the provision of the guarantee whichever occurs first;
- c) the bank agrees to pay the guaranteed sum without reference to the applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent; and
- d) the bank's obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required.

Any deferred or outstanding component of the section 94A levy will be adjusted in accordance with clause 3.13 of the plan. The applicant will be required to pay any charges associated with establishing or operating the bank guarantee. Council will not cancel the bank guarantee until the outstanding contribution as indexed and any accrued charges are paid.

C. Professional Engineering Details

The *Construction Certificate* plans and specifications, required by clause 139 of the Regulation, must include detailed *professional engineering* plans and specifications for all structural, electrical, hydraulic, hydro-geological, geotechnical, mechanical and civil work complying with this consent, approved plans, the statement of environmental effects and supporting documentation.

Detailed professional engineering plans and specifications must be submitted to the *Certifying Authority* with the application for any *Construction Certificate*.

C.3 Swimming and Spa Pools – Child Resistant Barriers

The *Construction Certificate* plans and specifications required by clause 139 of the Regulation must demonstrate compliance (by showing the proposed location of all child-resistant barriers and the resuscitation sign) with the provisions of the *Swimming Pools Act 1992*.

Note: A statement to the effect that isolation swimming pool fencing complying with AS1926 will be installed does not satisfy this condition. The location of the required barriers and the sign must be detailed upon the *Construction Certificate* plans.

C.4 Swimming and Spa Pools – Backwash

The *Construction Certificate* plans and specification required to be submitted pursuant to clause 139 of the Regulation must detail the connection of backwash to Sydney Waters sewer in compliance with clause 10.9 (Figure 10.2) of AS/NZS 3500.2.2:1996.

Note: The plans must show the location of Sydney Waters sewer, the yard gully or any new connection to the sewer system including a detailed cross section of the connection complying with clause 10.9 (Figure 10.2) of AS/NZS 3500.2.2:1996.

Note: The discharge of backwash water to any stormwater system is water pollution and an offence under the *Protection of the Environment Operations Act 1997*. The connection of any backwash pipe to any stormwater system is an offence under the *Protection of the Environment Operations Act 1997*.

C.5. Acoustic Certification of Mechanical Plant & Equipment

The *Construction Certificate* plans and specification required to be submitted pursuant to clause 139 of the Regulation must be accompanied by a certificate from a *professional engineer* (acoustic engineer) certifying that noise from the operation of mechanical plant and equipment will not exceed the background noise level when measured at any boundary of the site.

Where sound attenuation is required this must be detailed.

Note: Further information including lists of Acoustic Engineers can be obtained from:

- 1. Australian Acoustical Society**—professional society of noise-related professionals ([www.acoustics.asn.au /index.php](http://www.acoustics.asn.au/index.php)).
- 2. Association of Australian Acoustical Consultants**—professional society of noise related professionals (www.aaac.org.au).

C. Amended Landscape Plan

A Landscape Plan, prepared by a qualified Landscape Architect or Landscape Designer, to a scale of 1:100 or 1:200, conforming to the conditions of this Development Consent is to be submitted to Council for approval prior to issue of the Construction Certificate. The plan must include a detailed planting schedule, which must include species listed by botanical and common names, quantities of each species, pot sized, and the estimated size of the plant at maturity.

D. Conditions which must be satisfied prior to the commencement of any development work

D.1 Compliance with Building Code of Australia and insurance requirements under the Home Building Act 1989

For the purposes of section 80A (11) of the Act, the following conditions are prescribed in relation to a development consent for development that involves any building work:

- a) that the work must be carried out in accordance with the requirements of the Building Code of Australia,

- b) in the case of residential building work for which *the Home Building Act 1989* requires there to be a contract of insurance in force in accordance with Part 6 of that Act, that such a contract of insurance is in force before any building work authorised to be carried out by the consent commences.

This condition does not apply:

- c) to the extent to which an exemption is in force under clause 187 or 188, subject to the terms of any condition or requirement referred to in clause 187 (6) or 188 (4),
or
d) to the erection of a temporary building.

In this condition, a reference to the *BCA* is a reference to that code as in force on the date the application for the relevant construction certificate is made.

Note: This condition must be satisfied prior to commencement of any work in relation to the contract of insurance under the Home Building Act 1989. This condition also has effect during the carrying out of all building work with respect to compliance with the Building Code of Australia.

D.2 Site Signs

The *Principal Contractor* or *owner builder* must ensure that the sign required by clauses 98A and 227A of the *Regulation* is erected and maintained at all times.

“Erection of signs

- (1) For the purposes of section 80A (11) of the *Act*, the requirements of subclauses (2) and (3) are prescribed as conditions of a development consent for development that involves any building work, subdivision work or demolition work.
- (2) A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:
 - (a) showing the name, address and telephone number of the principal certifying authority for the work, and
 - (b) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
 - (c) stating that unauthorised entry to the work site is prohibited.
- (3) Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.
- (4) This clause does not apply in relation to building work, subdivision work or demolition work that is carried out inside an existing building that does not affect the external walls of the building.
- (5) This clause does not apply in relation to Crown building work that is certified, in accordance with section 116G of the *Act*, to comply with the technical provisions of the State’s building laws.”

Note: *PCA* and *principal contractors* must also ensure that signs required by this clause are erected and maintained (see clause 227A which imposes a penalty exceeding \$1,000).

Note: If *Council* is appointed as the *PCA* it will provide the sign to the *principal contractor* or *owner builder* who must ensure that the sign is erected and maintained as required by Clause 98A of the *Regulation*.

D.3 Toilet Facilities

Toilet facilities are to be provided, at or in the vicinity of the work site on which work involved in the erection or demolition of a building is being carried out, at the rate of one toilet for every 20 persons or part of 20 persons employed at the site.

Each toilet provided:

- a) must be a standard flushing toilet, and
- b) must be connected to a public sewer, or
- c) if connection to a public sewer is not practicable, to an accredited sewage management facility approved by the council, or
- d) if connection to a public sewer or an accredited sewage management facility is not practicable, to some other sewage management facility approved by the council.

The provision of toilet facilities in accordance with this condition must be completed before any other work is commenced.

In this condition:

accredited sewage management facility means a sewage management facility to which Division 4A of Part 3 of the *Local Government (Approvals) Regulation 1993* applies, being a sewage management facility that is installed or constructed to a design or plan the subject of a certificate of accreditation referred to in clause 95B of the *Local Government (Approvals) Regulation 1993*.

approved by the council means the subject of an approval in force under Division 1 of Part 3 of the *Local Government (Approvals) Regulation 1993*.

public sewer has the same meaning as it has in the *Local Government (Approvals) Regulation 1993*.

sewage management facility has the same meaning as it has in the *Local Government (Approvals) Regulation 1993*.

Note: This condition does not set aside the requirement to comply with Workcover NSW requirements.

D.4 Erosion and Sediment Controls – Installation

The *principal contractor* or *owner builder* must install and maintain water pollution, erosion and sedimentation controls in accordance with:

- a) The *Soil and Water Management Plan* if required under this consent;
- b) “*Do it Right On Site, Soil and Water Management for the Construction Industry*” published by the Southern Sydney Regional Organisation of Councils, 2001; and
- c) “*Managing Urban Stormwater - Soils and Construction*” published by the NSW Department of Housing 4th Edition” (“The Blue Book”).

Where there is any conflict The Blue Book takes precedence.

Note: The International Erosion Control Association – Australasia (<http://www.austieca.com.au/>) lists consultant experts who can assist in ensuring compliance with this condition. Where Soil and Water Management Plan is required for larger projects it is recommended that this be produced by a member of the International Erosion Control Association – Australasia.

Note: The “Do it Right On Site, Soil and Water Management for the Construction Industry” publications can be down loaded free of charge from www.woollahra.nsw.gov.au.

Note: A failure to comply with this condition may result in penalty infringement notices, prosecution, notices and orders under the Act and/or the *Protection of the Environment Operations Act 1997* **without any further warning**. It is a criminal offence to cause, permit or allow pollution.

Note: Section 257 of the *Protection of the Environment Operations Act 1997* provides inter alia that “the occupier of premises at or from which any pollution occurs is taken to have caused the pollution”

Warning, Irrespective of this condition any person occupying the site may be subject to proceedings under the *Protection of the Environment Operations Act 1997* where pollution is caused, permitted or allowed as the result of their occupation of the land being developed.

D.5 Building - Construction Certificate, Appointment of Principal Certifying Authority, Appointment of Principal Contractor and Notice of Commencement (s81A(2) of the Act)

The erection of the building in accordance with this development consent must not be commenced until:

- (c) a construction certificate for the building work has been issued by the consent authority, the council (if the council is not the consent authority) or an accredited Certifier, and
- (d) the person having the benefit of the development consent has:

appointed a principal certifying authority for the building work, and

notified the principal certifying authority that the person will carry out the building work as an owner-builder, if that is the case, and

- (b1) the principal certifying authority has, no later than 2 days before the building work commences:

notified the consent authority and the council (if the council is not the consent authority) of his or her appointment, and

notified the person having the benefit of the development consent of any critical stage inspections and other inspections that are to be carried out in respect of the building work, and

- (b2) the person having the benefit of the development consent, if not carrying out the work as an owner-builder, has:

appointed a principal contractor for the building work who must be the holder of a contractor licence if any residential building work is involved, and

notified the principal certifying authority of any such appointment, and

unless that person is the principal contractor, notified the principal contractor of any critical stage inspections and other inspections that are to be carried out in respect of the building work, and

given at least 2 days' notice to the council of the person's intention to commence the erection of the building.

Note: *building* has the same meaning as in section 4 of the *Act* and includes part of a building and any structure or part of a structure.

Note: *new building* has the same meaning as in section 109H of the *Act* and includes an altered portion of, or an extension to, an existing building.

Note: The commencement of demolition works associated with an altered portion of, or an extension to, an existing building is considered to be the commencement of building work requiring compliance with section 82A(2) of the *Act* (including the need for a *Construction Certificate*) prior to any demolition work. See: *Over our Dead Body Society Inc v Byron Bay Community Association Inc* [2001] NSWLEC 125.

Note: *Construction Certificate* Application, *PCA Service Agreement* and *Notice of Commencement* forms can be downloaded from Council's website www.woollahra.nsw.gov.au.

Note: It is an offence for any person to carry out the erection of a *building* in breach of this condition and in breach of section 81A(2) of the Act.

D.6 Notification of Home Building Act 1989 requirements

- (1) For the purposes of section 80A (11) of the Act, the requirements of this condition are prescribed as conditions of a development consent for development that involves any residential building work within the meaning of the Home Building Act 1989.
- (2) Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the principal certifying authority for the development to which the work relates (not being the council) has given the council written notice of the following information:
 - (a) in the case of work for which a *principal contractor* is required to be appointed:
 - (i) the name and licence number of the principal contractor, and
 - (ii) the name of the insurer by which the work is insured under Part 6 of that Act,
 - (b) in the case of work to be done by an owner-builder:
 - (i) the name of the owner-builder, and
 - (ii) if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.
- (3) If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under subclause (2) becomes out of date, further work must not be carried out unless the principal certifying authority for the development to which the work relates (not being the council) has given the council written notice of the updated information.
- (4) This clause does not apply in relation to Crown building work that is certified, in accordance with section 116G of the Act, to comply with the technical provisions of the State's building laws.

E. Conditions which must be satisfied during any development work

E.1 Compliance with Building Code of Australia and insurance requirements under the Home Building Act 1989

For the purposes of section 80A (11) of the Act, the following condition is prescribed in relation to a development consent for development that involves any building work:

- a) that the work must be carried out in accordance with the requirements of the Building Code of Australia,
- b) in the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, that such a contract of insurance is in force before any building work authorised to be carried out by the consent commences.

This condition does not apply:

- a) to the extent to which an exemption is in force under clause 187 or 188, subject to the terms of any condition or requirement referred to in clause 187 (6) or 188 (4) of the Regulation, or
- b) to the erection of a temporary building.

In this clause, a reference to the BCA is a reference to that Code as in force on the date the application for the relevant construction certificate is made.

E.2 Compliance with Australian Standard for Demolition

Demolition of buildings and structures must comply with Australian Standard AS 2601—1991: The Demolition of Structures, published by Standards Australia, and as in force at 1 July 1993.

E.3 Requirement to notify about new evidence

Any new information which comes to light during remediation, demolition or construction works which has the potential to alter previous conclusions about site contamination, heritage significance, threatened species or other relevant matters must be immediately notified to Council and the Principal Certifying Authority.

E.4 Critical Stage Inspections

Critical stage inspections must be called for by the *principal contractor* or *owner builder* as required by the PCA, any PCA service agreement, the *Act* and the *Regulation*.

Work must not proceed beyond each critical stage until the PCA is satisfied that work is proceeding in accordance with this consent, the Construction Certificate(s) and the *Act*. *critical stage inspections* means the inspections prescribed by the *Regulations* for the purposes of section 109E(3)(d) of the *Act* or as required by the *PCA* and any PCA Service Agreement.

Note: The PCA may require inspections beyond mandatory critical stage inspections in order that the PCA be satisfied that work is proceeding in accordance with this consent.

Note: The PCA may, in addition to inspections, require the submission of *Compliance Certificates*, survey reports or evidence of suitability in accordance with Part A2.2 of the BCA in relation to any matter relevant to the development.

E.5 Hours of Work –Amenity of the neighbourhood

- a) No *work* must take place on any Sunday or public holiday,
- b) No *work* must take place before 7am or after 5pm any weekday,
- c) No *work* must take place before 7am or after 1pm any Saturday, and
- d) No piling, piling, cutting, boring, drilling, rock breaking, rock sawing, jack hammering or bulk excavation of land or loading of material to or from trucks must take place before 9am or after 4pm any weekday, or before 9am or after 1pm any Saturday.
- e) No rock excavation being cutting, boring, drilling, breaking, sawing, jack hammering or bulk excavation of rock, must occur without a 15 minute break every hour.

This condition has been imposed to mitigate the impact of work upon the amenity of the neighbourhood. Impact of work includes, but is not limited to, noise, vibration, dust, odour, traffic and parking impacts.

- Note:** The use of noise and vibration generating plant and equipment and vehicular traffic, including trucks in particular, significantly degrade the amenity of neighbourhoods and more onerous restrictions apply to these activities. This more invasive work generally occurs during the foundation and bulk excavation stages of development. If you are in doubt as to whether or not a particular activity is considered to be subject to the more onerous requirement (9am to 4pm weekdays and 9am to 1pm Saturdays) please consult with Council.
- Note:** Each and every breach of this condition by any person may be subject to separate penalty infringement notice or prosecution.
- Note:** The delivery and removal of plant, equipment and machinery associated with wide loads subject to RTA and Police restrictions on their movement outside the approved hours of work will be considered on a case by case basis.
- Note:** Compliance with these hours of work does not affect the rights of any person to seek a remedy to offensive noise as defined by the *Protection of the Environment Operations Act 1997*, the *Protection of the Environment Operations (Noise Control) Regulation 2000*.
- Note:** EPA Guidelines can be downloaded from <http://www.epa.nsw.gov.au/noise/nglg.htm>.
- Note:** See http://www.epa.nsw.gov.au/resources/ci_build_sheet7.pdf

E.6 Maintenance of Vehicular and Pedestrian Safety and Access

The *principal contractor* or *owner builder* and any other person acting with the benefit of this consent must:

- a) Not erect or maintain any gate or fence swing out or encroaching upon the road or the footway.
- b) Not use the road or footway for the storage of any article, material, matter, waste or thing.
- c) Not use the road or footway for any *work*.
- d) Keep the road and footway in good repair free of any trip hazard or obstruction.
- e) Not stand any plant and equipment upon the road or footway.

This condition does not apply to the extent that a permit or approval exists under the section 73 of the Road Transport (Safety and Traffic Management) Act 1999, section 138 of the Roads Act 1993 or section 94 of the Local Government Act 1993 except that at all time compliance is required with:

- a) Australian Standard AS 1742 (Set) Manual of uniform traffic control devices and all relevant parts of this set of standards.
- b) Australian Road Rules to the extent they are adopted under the *Road Transport (Safety and Traffic Management) (Road Rules) Regulation 1999*.

Note: Section 73 of the *Road Transport (Safety and Traffic Management) Act 1999* allows the Police to close any road or road related area to traffic during any temporary obstruction or danger to traffic or for any temporary purpose. Any road closure requires Police approval.

Note: Section 138 of the *Roads Act 1993* provides that a person must not:

- (a) erect a structure or carry out a work in, on or over a public road, or
- (b) dig up or disturb the surface of a public road, or
- (c) remove or interfere with a structure, work or tree on a public road, or
- (d) pump water into a public road from any land adjoining the road, or
- (e) connect a road (whether public or private) to a classified road, otherwise than with the consent of the appropriate roads authority.

Note: Section 68 of the *Local Government Act 1993* provides that a person may carry out certain activities only with the prior approval of the council including:

Part C Management of Waste:

“1 For fee or reward, transport waste over or under a public place

2 Place waste in a public place

3 Place a waste storage container in a public place.”

Part E Public roads:

“1 Swing or hoist goods across or over any part of a public road by means of a lift, hoist or tackle projecting over the footway

2 Expose or allow to be exposed (whether for sale or otherwise) any article in or on or so as to overhang any part of the road or outside a shop window or doorway abutting the road, or hang an article beneath an awning over the road.”

Any work in, on or over the Road or Footway requires *Council* Approval and in the case of classified roads the NSW Roads and Traffic Authority. Road includes that portion of the road uses as a footway.

E.7 Replacement trees which must be planted

The following compensatory replacement plantings must be planted to ensure the preservation of the landscape character of the area.

Species/Type	Planting Location	Container Size or Size of Tree (@ time of planting)	Minimum Dimensions at Maturity
<i>Magnolia grandiflora</i> Bull Bay Magnolia	As indicated in Proposed Ground Floor Plan Caroline Pidcock (4.10.06).	100 Litre	8 (h) x6 (w)

E.8 Amenity Landscaping

The *owner* or *principal contractor* must install all approved amenity landscaping (screen planting, soil stabilisation planting, etc.) prior to any occupation or use of the site.

E.9 Landscaping

All landscape work including all planting must be completed by the principal contractor or owner in compliance with the approved landscape plan, arborist report, transplant method statement and tree management plan. The principal contractor or owner must provide to PCA a works-as-executed landscape plan and certification from a qualified landscape architect/designer, horticulturist and/or arborist as applicable that the works as completed comply with this consent.

E.10 Maintenance of Landscaping

All landscaping must be maintained in accordance with the approved landscape plans. Any alteration from that plan will require the prior written consent of Council.

E.11 Erosion and Sediment Controls – Maintenance

The *principal contractor* or *owner builder* must maintain water pollution, erosion and sedimentation controls in accordance with:

- a) The Soil and Water Management Plan required under this consent;

- b) “*Do it Right On Site, Soil and Water Management for the Construction Industry*” published by the Southern Sydney Regional Organisation of Councils, 2001; and
- c) “*Managing Urban Stormwater - Soils and Construction*” published by the NSW Department of Housing 4th Edition (“*The Blue Book*”).

Where there is any conflict The Blue Book takes precedence.



- Note 1:** A failure to comply with this condition may result in penalty infringement notices, prosecution, notices and orders under the Act and/or the Protection of the Environment Operations Act 1997 without any further warning. It is a criminal offence to cause, permit or allow pollution.
- Note 2:** Section 257 of the Protection of the Environment Operations Act 1997 provides that “the occupier of premises at or from which any pollution occurs is taken to have caused the pollution”.
- Warning,** Irrespective of this condition any person occupying the site may be subject to proceedings under the Protection of the Environment Operations Act 1997 where pollution is caused, permitted or allowed as the result of the occupation of the land being developed whether or not they actually cause the pollution.

E.12 Disposal of site water during construction

The principal contractor or owner builder must ensure:

- a) Prior to pumping any water into the road or public stormwater system that approval is obtained from *Council* under section 138(1)(d) of the *Roads Act 1993*;
- b) That *water pollution*, as defined by the *Protection of the Environment Operations Act 1997*, does not occur as the result of the discharge to the road, public stormwater system or other place or any site water;
- c) That stormwater from any roof or other impervious areas is linked, via temporary downpipes and stormwater pipes, to a Council approved stormwater disposal system immediately upon completion of the roof installation or work creating other impervious areas.

Note: This condition has been imposed to ensure that adjoining and neighbouring land is not adversely affected by unreasonable overland flows of stormwater and that site water does not concentrate water such that they cause erosion and water pollution.

E.13 Filling of site

To the extent that this consent permits filling of the site such fill must be *virgin excavated natural material* (“*VENM*”).

VENM means “*Virgin excavated natural material (such as clay, gravel, sand, soil and rock) that is not mixed with any other type of waste and which has been excavated from areas of land that are not contaminated with human-made chemicals as a result of industrial, commercial, mining or agricultural activities and which do not contain sulphidic ores or soils.*”

Note: This definition is the same as in Schedule 1 of the *Protection of the Environment Operations Act 1997*, Appendix IX: Types of waste.

Note: Sulphidic ores and soils are commonly known as Acid Sulphate Soils.

Note: If a person transports waste to a place (the site) that cannot lawfully be used as a waste facility for that waste: (a) the person, and, (b) if the person is not the owner of the waste, the owner, are each guilty of an offence under section 143 of the *Protection of the Environment Operations Act 1997*.

Note: A person who is the owner or occupier (principal contractor) of any land that cannot lawfully be used as a waste facility and who permits the land to be used as a waste facility is guilty of an offence under section 144 of the *Protection of the Environment Operations Act 1997*.

Note: Additional information is available from the following websites:

Illegal waste dumping - <http://www.epa.nsw.gov.au/waste/dumping.htm>

Is that fill legal? <http://www.epa.nsw.gov.au/resources/012648web.epa%20fill.dl%20bro.pdf>

E.14 Site Cranes

Site Crane(s) and hoist(s) may be erected within the boundary of the land being developed subject to compliance with Australian Standards AS 1418, AS 2549 and AS 2550 and all relevant parts to these standards.

Cranes must not swing or hoist over any public place unless the *principal contractor* or *owner builder* have the relevant approval under the *Local Government Act 1993*, *Crown Lands Act 1989* or *Roads Act 1993*.

The crane must not be illuminated outside approved working hours other than in relation to safety beacons required by the Civil Aviation Safety Authority under the *Civil Aviation Act 1988* (Cth).

No illuminated sign(s) must be erected upon or displayed upon any site crane.

Note: Where it is proposed to swing a crane over a public place the *principal contractor* or *owner builder* must make a separate application to Council under section 68 of the *Local Government Act 1993* and obtain activity approval from Council prior to swinging or hoisting over the public place.

Note: Where it is proposed to swing a crane over private land the consent of the owner of that private land is required. Alternatively, the *principal contractor* or *owner builder* must obtain an access order under the *Access to Neighbouring Land Act 2000* or easement under section 88K of the *Conveyancing Act 1919* or section 40 of the *Land & Environment Court Act 1979* as appropriate. The encroachment of cranes or the like is a civil matter of trespass and encroachment. Council does not adjudicate or regulate such trespasses or encroachments.

E.15 Placement and use of Skip Bins

The *principal contractor* or *owner builder* must ensure that all waste storage containers, including but not limited to skip bins, must be stored within the site unless:

- a) Activity Approval has been issued by Council under section 94 of the *Local Government Act 1993* to place the waste storage container in a public place, and
- b) Where located on the road it is located only in a positions where a vehicle may lawfully park in accordance with the Australian Road Rules to the extent they are adopted under the *Road Transport (Safety and Traffic Management) (Road Rules) Regulation 1999*, and

Note: Waste storage containers must not be located on the footpath without a site specific activity approval. Where such site specific activity approval is granted a 1.5m wide clear path of travel is maintained free of any trip hazards.

E.16 Prohibition of burning

There must be no burning of any waste or other materials. The burning of CCA (copper chrome arsenate) or PCP (pentachlorophenol) treated timber is prohibited in all parts of NSW. All burning is prohibited in the Woollahra local government area.

Note: Pursuant to the *Protection of the Environment Operations (Control of Burning) Regulation 2000* all burning (including burning of vegetation and domestic waste) is prohibited except with approval. No approval is granted under this consent for any burning.

E.17 Dust Mitigation

Dust mitigation must be implemented in accordance with “*Dust Control - Do it right on site*” published by the Southern Sydney Regional Organisation of Councils.

This generally requires:

- a) Dust screens to all hoardings and site fences.
- b) All stockpiles or loose materials to be covered when not being used.
- c) All equipment, where capable, being fitted with dust catchers.
- d) All loose materials being placed bags before placing into waste or skip bins.
- e) All waste and skip bins being kept covered when not being filled or emptied.
- f) The surface of excavation work being kept wet to minimise dust.
- g) Landscaping incorporating trees, dense shrubs and grass being implemented as soon as practically possible to minimise dust.

Note 1: “*Dust Control - Do it right on site*” can be down loaded free of charge from Council’s web site www.woollahra.nsw.gov.au or obtained from Council’s office.

Note 2: Special precautions must be taken when removing asbestos or lead materials from development sites. Additional information can be obtained from www.workcover.nsw.gov.au and www.epa.nsw.gov.au . Other specific condition and advice may apply.

Note 3: Demolition and construction activities may affect local air quality and contribute to urban air pollution. The causes are dust, smoke and fumes coming from equipment or activities, and airborne chemicals when spraying for pest management. Precautions must be taken to prevent air pollution.

E.18 Swimming and Spa Pools – Temporary Child Resistant Barriers and other matters

Temporary child-resistant barriers must be installed in compliance with the *Swimming Pools Act 1992* where any swimming pool or spa pool as defined by the *Swimming Pools Act 1992* contains more than 300mm in depth of water at any time. Permanent child-resistant barriers must be installed in compliance with the *Swimming Pools Act 1992* as soon as practical.

Backwash and any temporary dewatering from any swimming pool or spa pool as defined by the *Swimming Pools Act 1992* must be discharged to the sewer in compliance with clause 10.9 (Figure 10.2) of AS/NZS 3500.2.2:1996.

Note: This condition does not prevent Council from issuing an order pursuant to section 23 of the *Swimming Pool Act 1992* or taking such further action as necessary for a breach of this condition or the *Swimming Pools Act 1992*.

F. Conditions which must be satisfied prior to any occupation or use of the building (Part 4A of the Act and Part 8 Division 3 of the Regulation)

F.1 Occupation Certificate (section 109M of the Act)

A person must not commence occupation or use of the whole or any part of a new building (within the meaning of section 109H (4) of the *Act*) unless an occupation certificate has been issued in relation to the building or part.

Note: new building includes an altered portion of, or an extension to, an existing building.

F.2 Amenity Landscaping

The *owner* or *principal contractor* must install all approved amenity landscaping (screen planting, soil stabilisation planting, etc.) prior to any occupation or use of the site.

Note: This condition has been imposed to ensure that the environmental impacts of the development are mitigated by approved landscaping prior to any occupation of the development.
Standard Condition: F6

F.3 Inspection, Certification and Registration of Regulated Systems

Prior to the issue of any *Occupation Certificate* or occupation or use of part of the building serviced by a *regulated system* the *principal contractor* or *owner builder* must submit to the satisfaction of PCA certification by a '*competent person*' that the regulated system as installed can operate as required by Clause 9 of the *Public Health (Microbial Control) Regulation, 2000*.

The owner must register the regulated systems with Council and provide the PCA with evidence of registration pursuant to Clause 15 of the *Public Health (Microbial Control) Regulation, 2000*.

Note: *Regulated System* has the same mean as in the Public Health Act 1991.

Note: *Competent person* has the same meaning as in Clause 9(3) of the *Public Health (Microbial Control) Regulation, 2000*.

Note: The NSW Code of Practice for the Control of Legionnaires' Disease can be down loaded free from: http://www.health.nsw.gov.au/pubs/2004/pdf/legionnaires_disease.pdf

F.4 Swimming and Spa Pools – Permanent Child Resistant Barriers and other matters

Prior to any occupation or use of the development and prior to filling any swimming pool as defined by the *Swimming Pool Act 1992*:

- a) Permanent child-resistant barriers must be installed in compliance with the *Swimming Pools Act 1992*.

- b) The *Principal Contractor* or *owner* must apply for and obtain a Compliance Certificate under section 24 of the *Swimming Pools Act 1992*.
- c) Public Pools must comply with the NSW Health Public Swimming Pool and Spa Pool Guidelines in force at that time and private pools are encouraged to comply with the same standards as applicable.
- d) Water recirculation and filtration systems must be installed in compliance with AS 1926.3-2003:*Swimming pool safety - Water recirculation and filtration systems*.

Backwash must be discharged to the sewer in compliance with clause 10.9 (Figure 10.2) of AS/NZS 3500.2.2:1996.

- e) Water recirculation and filtration systems must be connected to the electricity supply by a timer that limits the systems operation such that it does not operate:
- f) before 8 am or after 8 pm on any Sunday or public holiday, or before 7 am or after 8 pm on any other day.

Note: The NSW Health Public Swimming Pool and Spa Pool Guidelines can be down loaded free from:
<http://www.health.nsw.gov.au/public-health/ehb/general/pools/poolguidelines.pdf>

G. Conditions which must be satisfied prior to the issue of any Subdivision Certificate

No relevant conditions.

H. Conditions which must be satisfied prior to the issue of a Final Occupation Certificate (s109C(1)(c))

No relevant conditions.

I. Conditions which must be satisfied during the ongoing use of the development

I.1 Maintenance of Landscaping

All landscaping must be maintained in general accordance with this consent.

This condition does not prohibit the planting of additional trees or shrubs subject that they are native species endemic to the immediate locality.

Reason: This condition has been imposed to ensure that the landscaping design intent is not eroded over time by the removal of landscaping or inappropriate exotic planting.

Note: This condition also acknowledges that development consent is not required to plant vegetation and that over time additional vegetation may be planted to replace vegetation or enhance the amenity of the locality. Owners should have regard to the amenity impact of trees upon the site and neighbouring land. Further, drought proof vegetation being native species endemic to the immediate locality is encouraged. Suggested native species endemic to the immediate locality are listed in the Brochure Titled "Local Native Plants for Sydney's Eastern Suburbs" published by Woollahra, Waverley, Randwick and Botany Bay Councils.

I.2 Swimming and Spa Pools – Maintenance

Swimming and Spa Pools must be maintained:

- (a) in compliance with the *Swimming Pools Act 1992* with regard to the provision of child-resistant barriers and resuscitation signs;

- (b) in compliance with the NSW Health “Public Swimming Pool and Spa Pool Guidelines” in force at that time. Private pools are encouraged to comply with the same standards as applicable;
- (c) in compliance with AS 1926.3-2003:Swimming pool safety - Water recirculation and filtration systems ;
- (d) with backwash being discharged to the sewer in compliance with clause 10.9 (Figure 10.2) of AS/NZS 3500.2.2:1996, and
- (e) with a timer that limits the recirculation and filtration systems operation such that it does not emit noise that can be heard within a habitable room in any other residential premises (regardless of whether any door or window to that room is open):
before 8 am or after 8 pm on any Sunday or public holiday, or
before 7 am or after 8 pm on any other day.

Note: Child-resistant barriers, resuscitation signs, recirculation and filtration systems and controls systems require regular maintenance to ensure that life safety, health and amenity standards are maintained.

Note: The NSW Health Public Swimming Pool and Spa Pool Guidelines can be down loaded free from:
<http://www.health.nsw.gov.au/public-health/ehb/general/pools/poolguidelines.pdf>

I.3 Outdoor lighting – Residential

Outdoor lighting must comply with AS 4282-1997: Control of the obtrusive effects of outdoor lighting. The maximum luminous intensity from each luminaire must not exceed the level 1 control relevant under table 2.2 of AS 4282. The maximum illuminance and the threshold limits must be in accordance with table 2.1 of AS 4282.

Reason: This condition has been imposed to protect the amenity of neighbours and limit the obtrusive effects of outdoor lighting in public places.

Note: This condition has been imposed to control the obtrusive effects of outdoor lighting.

J. Miscellaneous Conditions

No relevant conditions.

There being no further business the meeting concluded at 4.43pm.

We certify that the pages numbered 1 to 69 inclusive are the Minutes of the Application Assessment Panel Meeting held on 27 February 2007 and confirmed by the Application Assessment Panel on 6 March 2007 as correct.

Chairperson

Secretary